

Adams County Area, Parts of Adams and Denver Counties, Colorado

UIC—Ulm loam, 3 to 5 percent slopes

Map Unit Setting

National map unit symbol: 34x4
Elevation: 4,000 to 5,600 feet
Mean annual precipitation: 12 to 14 inches
Mean annual air temperature: 48 to 52 degrees F
Frost-free period: 125 to 155 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Ulm and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ulm

Setting

Landform: Plains
Landform position (three-dimensional): Talf
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Residuum weathered from sandstone and shale

Typical profile

H1 - 0 to 7 inches: loam
H2 - 7 to 13 inches: silty clay
H3 - 13 to 30 inches: clay
H4 - 30 to 48 inches: clay loam
H5 - 48 to 52 inches: unweathered bedrock

Properties and qualities

Slope: 3 to 5 percent
Depth to restrictive feature: 40 to 60 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat):
Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 15 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Moderate (about 8.2 inches)

Interpretive groups

Land capability classification (irrigated): 3e

Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: C
Ecological site: Loamy Plains (R067BY002CO)
Hydric soil rating: No

Minor Components

Renohill

Percent of map unit: 13 percent
Hydric soil rating: No

Shingle

Percent of map unit: 5 percent
Hydric soil rating: No

Apishapa

Percent of map unit: 2 percent
Landform: Swales
Hydric soil rating: Yes

Data Source Information

Soil Survey Area: Adams County Area, Parts of Adams and Denver Counties, Colorado

Survey Area Data: Version 13, Sep 22, 2016