

FORM
2A

Rev
04/18

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401809209

Date Received:

12/03/2018

Oil and Gas Location Assessment

☒ New Location ☐ Refile ☐ Amend Existing Location Location#: _____

This Oil and Gas Location Assessment is to be submitted to the COGCC for approval prior to any ground disturbance activity associated with oil and gas operations. Approval of this Oil and Gas Location Assessment will allow for the construction of the below specified Location; however, it does not supersede any land use rules applied by the local land use authority. Please see the COGCC website at <http://cogcc.state.co.us/> for all accompanying information pertinent this Oil and Gas Location Assessment.

Location ID:

461821

Expiration Date:

02/10/2022

☒ This location assessment is included as part of a permit application.

CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # _____
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

Operator

Operator Number: 10670

Name: MALLARD EXPLORATION LLC

Address: 1400 16TH STREET SUITE 300

City: DENVER State: CO Zip: 80202

Contact Information

Name: Erin Mathews

Phone: (720) 543 7951

Fax: ()

email: emathews@mallardexploration.com

FINANCIAL ASSURANCE

☒ Plugging and Abandonment Bond Surety ID (Rule 706): 20170115 ☐ Gas Facility Surety ID (Rule 711): _____

☐ Waste Management Surety ID (Rule 704): _____

LOCATION IDENTIFICATION

Name: Canvasback Number: Pad

County: WELD

Quarter: NWSW Section: 32 Township: 9N Range: 60W Meridian: 6 Ground Elevation: 4945

Define a single point as a location reference for the facility location. When the location is to be used as a well site then the point shall be a well location.

Footage at surface: 2481 feet FSL from North or South section line

629 feet FWL from East or West section line

Latitude: 40.705475 Longitude: -104.123672

PDOP Reading: 4.3 Date of Measurement: 10/19/2018

Instrument Operator's Name: Brian Hopkinson

RELATED REMOTE LOCATIONS

(Enter as many Related Locations as necessary. Enter the Form 2A document # only if there is no established COGCC Location ID#)

This proposed Oil and Gas Location is:

LOCATION ID #

FORM 2A DOC #

FACILITIES

Indicate the number of each type of oil and gas facility planned on location

Wells	14	Oil Tanks*	28	Condensate Tanks*		Water Tanks*	14	Buried Produced Water Vaults*	
Drilling Pits		Production Pits*		Special Purpose Pits		Multi-Well Pits*		Modular Large Volume Tanks	2
Pump Jacks	14	Separators*		Injection Pumps*		Cavity Pumps*		Gas Compressors*	2
Gas or Diesel Motors*	14	Electric Motors	14	Electric Generators*	2	Fuel Tanks*		LACT Unit*	2
Dehydrator Units*		Vapor Recovery Unit*	4	VOC Combustor*	4	Flare*		Pigging Station*	

OTHER FACILITIES*

Other Facility Type

Number

Vapor Recovery Tower	1
Emission Control Devices	4

Those facilities indicated by an asterisk () shall be used to determine the distance from the Production Facility to the nearest cultural feature on the Cultural Setbacks Tab.

Per Rule 303.b.(3)C, description of all oil, gas, and/or water pipelines:

3" welded steel flowlines from wellheads to separators carrying oil, gas and water.
3" welded steel gas supply line from compressors to wellheads.

CONSTRUCTION

Date planned to commence construction: 02/01/2019 Size of disturbed area during construction in acres: 16.40

Estimated date that interim reclamation will begin: 08/01/2019 Size of location after interim reclamation in acres: 8.50

Estimated post-construction ground elevation: 4945

DRILLING PROGRAM

Will a closed loop system be used for drilling fluids: Yes

Is H₂S anticipated? No

Will salt sections be encountered during drilling: No

Will salt based mud (>15,000 ppm Cl) be used? No

Will oil based drilling fluids be used? Yes

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Method: Commercial Disposal

Cutting Disposal: OFFSITE

Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

Centralized E&P Waste Management Facility ID, if applicable:

SURFACE & MINERALS & RIGHT TO CONSTRUCT

Name: <u>Shable Homestead LLC</u>	Phone: _____
Address: <u>12701 State Highway 60</u>	Fax: _____
Address: _____	Email: _____
City: <u>Milliken</u> State: <u>CO</u> Zip: <u>80543-9308</u>	

Surface Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian

Check all that apply. The Surface Owner: ☒ is the mineral owner

☒ is committed to an oil and Gas Lease

☒ has signed the Oil and Gas Lease

☐ is the applicant

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed from or produced to this Oil and Gas Location: Yes

The right to construct this Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

Date of Rule 306 surface owner consultation _____

CURRENT AND FUTURE LAND USE

Current Land Use (Check all that apply):				
Crop Land:	<input type="checkbox"/> Irrigated	<input type="checkbox"/> Dry land	<input type="checkbox"/> Improved Pasture	<input type="checkbox"/> Hay Meadow <input type="checkbox"/> CRP
Non-Crop Land:	<input checked="" type="checkbox"/> Rangeland	<input type="checkbox"/> Timber	<input type="checkbox"/> Recreational	<input type="checkbox"/> Other (describe): _____
Subdivided:	<input type="checkbox"/> Industrial	<input type="checkbox"/> Commercial	<input type="checkbox"/> Residential	

Future Land Use (Check all that apply):				
Crop Land:	<input type="checkbox"/> Irrigated	<input type="checkbox"/> Dry land	<input type="checkbox"/> Improved Pasture	<input type="checkbox"/> Hay Meadow <input type="checkbox"/> CRP
Non-Crop Land:	<input checked="" type="checkbox"/> Rangeland	<input type="checkbox"/> Timber	<input type="checkbox"/> Recreational	<input type="checkbox"/> Other (describe): _____
Subdivided:	<input type="checkbox"/> Industrial	<input type="checkbox"/> Commercial	<input type="checkbox"/> Residential	

CULTURAL DISTANCE INFORMATION

Provide the distance to the nearest cultural feature as measured from Wells or Production Facilities onsite.

	From WELL	From PRODUCTION FACILITY
Building:	5280 Feet	5280 Feet
Building Unit:	5280 Feet	5280 Feet
High Occupancy Building Unit:	5280 Feet	5280 Feet
Designated Outside Activity Area:	5280 Feet	5280 Feet
Public Road:	2621 Feet	2370 Feet
Above Ground Utility:	3160 Feet	2904 Feet
Railroad:	5280 Feet	5280 Feet
Property Line:	628 Feet	203 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of nearest Well or edge of nearest Production Facility to nearest of each cultural feature as described in Rule 303.b.(3)A.
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.
- For measurement purposes only, Production Facilities should only include those items with an asterisk(*) on the Facilities Tab.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:

- ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit.
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.
- Large UMA Facility - as defined in 100-Series Rules.

FOR MULTI-WELL PADS AND PRODUCTION FACILITIES WITHIN DESIGNATED SETBACK LOCATIONS ONLY:

- ☐ Check this box if this Oil and Gas Location has or will have Production Facilities that serve multiple wells (on or offsite) and the Production Facilities are proposed to be located less than 1,000 feet from a Building Unit. *(Pursuant to Rule 604.c.(2)E.i., the operator must evaluate alternative locations for the Production Facilities that are farther from the Building Unit, and determine whether those alternative locations were technically feasible and economically practicable for the same proposed development.)*
- ☐ By checking this box, I certify that no alternative placements for the Production Facilities, farther from the nearest Building Unit, were available based on the analysis conducted pursuant to Rule 604.c.(2)E.i.

In the space below, explain rationale for siting the multi-well Production Facility(ies) that supports your Rule 604.c.(2)E.i determination. Attach documentation that supports your determination to this Form 2A.

SOIL

List all soil map units that occur within the proposed location. attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.org/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: 40 - Nunn loam, 0 to 6 percent slopes

NRCS Map Unit Name: 56 - Renohill fine sandy loam, 6 to 9 percent slopes

NRCS Map Unit Name: _____

PLANT COMMUNITY:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☒

Plant species from: ☐ NRCS or, ☒ field observation Date of observation: 10/19/2018

List individual species:

Check all plant communities that exist in the disturbed area.

- ☒ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
☒ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
☐ Alpine (above timberline)
☐ Other (describe):

WATER RESOURCES

Is this a sensitive area: ☒ No ☐ Yes

Distance to nearest

downgradient surface water feature: 1382 Feet

water well: 2683 Feet

Estimated depth to ground water at Oil and Gas Location 73 Feet

Basis for depth to groundwater and sensitive area determination:

Location is not sensitive due to lack of proximate surface water features or domestic water wells.
Depth to groundwater taken from permit #271773.

Is the location in a riparian area: ☒ No ☐ Yes

Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes If yes attach permit.

Is the location within a Rule 317B Surface Water Supply Area buffer No

zone:

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified:

Is the Location within a Floodplain? ☒ No ☐ Yes Floodplain Data Sources Reviewed (check all that apply)

☒ Federal (FEMA)

☒ State

☐ County

☐ Local

☐ Other

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

WILDLIFE

☐ This location is included in a Wildlife Mitigation Plan

☐ This location was subject to a pre-consultation meeting with CPW held on _____

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of a Building Unit) and is in an Urban Mitigation Area
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments Manufacturer of MLVT: Hydrologistics
Size and Volume: Up to two (2) 157' diameter/42,000 BBLs
Anticipated time frame on site: 90 days

Since this location is not in a buffer zone, a Waste Management Plan and Facility Layout Drawing are not included.
No surface water within 1000', therefore no Hydrology Map is attached.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.
Signed: _____ Date: 12/03/2018 Email: regulatory@ascentgeomatics.com

Print Name: Justin Garrett Title: Regulatory Analyst

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  _____ Director of COGCC Date: 2/11/2019

Conditions Of Approval

All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.

<u>COA Type</u>	<u>Description</u>
-----------------	--------------------

--	--

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	General Housekeeping	804. Visual Impacts: All long term facility structures will be painted a color that enables the facilities to blend in with the natural background color of the landscape, as seen from a viewing distance and location typically used by the public. Maintain appearance with garbage clean-up; a trash bin will be located on site to accumulate waste by the personnel drilling the wells. Site will have unused equipment, trash and junk removed immediately.

2	Storm Water/Erosion Control	Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).
3	Material Handling and Spill Prevention	<p>1. Integrity testing of flowlines connecting wellheads to the separators: CONSTRUCTION PHASE: The flowlines that Operator uses are designed/constructed/tested to ASME B31.4 and API 1104 standards. Only materials with Material Test Reports (MTRs) provided by the pipeline supplier are used in the construction of the flowlines. Construction is tested with 100% x-ray and is hydrotested per the applicable ASME Code. OPERATIONS PHASE: Pressure testing of the flowlines is conducted on an annual basis. Additionally, Operator is already in compliance with 1104.i. Continuous Pressure Monitoring Requirements of the 1100 Series Flowline Regulations. Operator utilizes a series of standard operating procedures to define our flowline integrity testing program.</p> <p>2. Frequency on valve and fitting inspections: Operator's Lease Operators inspect all equipment on their locations at a minimum of once every 48 hours, but most sites are inspected every 24 hours. Valves and fittings inspections are part of the daily job duties of the lease operators. Any valve or fitting that is found to be leaking is either repaired immediately by the lease operator or shut-in procedures are implemented as described below. Additionally, lease operators conduct a documented monthly inspection of the facility and this includes inspection of all valves and fittings.</p> <p>3. Description of Lease Operator Inspections, Monthly Documented Inspections & Environmental Inspections: The Operator lease operator inspections are done as a routine part of the lease operators job. The lease operator would typically visit each of their assigned locations daily. They conduct a visual inspection of the facility which includes all valves, fittings, wellhead, tanks, vapor control systems and all connections. The lease operator also checks our Scada automation system for system pressures and flows. Pressure and flow sensors are placed on multiple points throughout the system and are specifically designed to measure the system for irregularities that would indicate a leak in the system or change in production of oil, water, or gas. The Scada system is also set-up with alarms that are triggered by anomalous pressure or flows. Low pressure warnings can activate automatic shut-in of the well and system. Lease operator inspections would note any leaks of either gas or fluids which triggers an immediate repair or shut-in. The Lease operators also conduct CDPHE Regulation 7– Audible, Visual, and Olfactory (AVO) inspections, which focus on the tanks and vapor control system. The Regulation 7 AVO is also a documented inspection. In addition, the sites are inspected with optical gas imaging cameras on a routine schedule, annually for compliance purposes with our Spill Prevention Containment and Countermeasures (SPCC) plan, depending on the status of reclamation the sites are also inspected on either a 14-day, 30-day, annual or rain triggered event in accordance with both the COGCC and the CDPHE Stormwater Management Plans (SWMP).</p> <p>4. Measures for when leaks are discovered: If we suspect a leak we shut in the well and hydrotest the line. If it passes, then the well is brought back into production. If there is an actual leak, the well is kept shut in while the leak is found and fixed. Not until the line has passed hydrotesting, would the well be brought back online.</p>

4	Construction	<p>Operator will have an MLVT Design Package, certified and sealed by a licensed professional engineer, which is on file in their office and available upon request. The site shall be prepared in accordance with the specifications of the design package prior to tank installation; including ensuring that proper compaction requirements have been met.</p> <p>The MLVT will be at least 75 feet from a wellhead, fired vessel, heater-treater, or a compressor with a rating of 200 horsepower or more. It will be placed at least 50 feet from a separator, well test unit, or other non-fired equipment.</p> <p>All liner seams will be welded and tested in accordance with applicable ASTM international standards.</p> <p>Operator will be present during initial filling of the MLVT and the contractor will supervise and inspect the MLVT for leaks during filling.</p> <p>Operator will comply with the testing and re-inspection requirements and associated written standard operating procedures (SOP) listed on the design package.</p> <p>Signs will be posted on the MLVT indicating that the contents are freshwater.</p> <p>The MLVT will be operated with a minimum of 1 foot of freeboard at all times.</p> <p>Access to the MLVT will be limited to operational personnel and authorized regulatory agency personnel.</p> <p>Operator or contractor will conduct daily visual inspections of the exterior wall and surrounding area for integrity deficiencies.</p> <p>Operator will have a contingency plan/emergency response plan associated with the MLVT and it is on file at their office.</p> <p>A fabric reinforced liner will be utilized. In the event that a tank breach were to occur, the fabric reinforced liner will prevent a "zippering" failure from occurring. The liner will meet the specifications per the design package.</p> <p>Operator acknowledges and will comply with the Colorado Oil & Gas Conservation Commission Policy on the Use of Modular Large Volume Tanks in Colorado dated June 13, 2014.</p>	
5	Emissions mitigation	<p>Operator has contracted with a third party to bring a gas sales lines to the location to send salable quality gas immediately down the sales line. In the event that a sales line connection is not available upon the completion of flowback, operator will follow the policy per the Notice to Operators "Rule 912 Venting or Flaring Produced Natural Gas". All salable quality gas shall be directed to the sales line as soon as practicable or shut in and conserved in accordance with Rule 805.b.(3)B.v.</p>	
6	Interim Reclamation	<p>Operator shall be responsible for segregating the topsoil, backfilling, re-compacting any backfill, reseeding, and re-contouring the surface of any disturbed area so as not to interfere with Owner's operations and shall reclaim such area to be returned to preexisting conditions as best as possible with control of all noxious weeds.</p>	

Total: 6 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401809209	FORM 2A SUBMITTED
401849664	ACCESS ROAD MAP
401849669	LOCATION DRAWING
401849672	LOCATION PICTURES
401849673	REFERENCE AREA MAP
401849675	REFERENCE AREA PICTURES
401849677	NRCS MAP UNIT DESC
401849680	NRCS MAP UNIT DESC
401849681	MULTI-WELL PLAN

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Permitting review complete, passed Final Review.	01/29/2019
OGLA	No Public Comments. OGLA task passed.	12/26/2018
OGLA	OGLA review completed. Waiting on Public Comment period.	12/21/2018
Permit	Passed completeness.	12/05/2018

Total: 4 comment(s)