

Enerplus Resources

				WELL:	Kenneth Thayer 1	FIELD:	Wildcat
				LOCATION:	SWSW Sec 29-T8N-R67E, Weld Co, CO 660' FSL - 660' FWL		
251' 415'	10 sks 352'	Fox Hills (base) 8-5/8"		ACCTG CODE:		STATUS:	DA
	25 sks			ELEVATION:	GL - 5,237'	API NO	05-123-08834
	443'			SPUD DATE:	8/20/1976	COMP DATE:	9/7/1976
				MEASURED TD:	9,164'	TVD:	9,164'
				SURF CSG:	8-5/8" 24# set at 415'. Cmtd with 330 sks.		
4,152'		Sussex Top		PROD CSG:	N/A 7-7/8" open hole to 9,164'		
4,541'		Shannon Top		FORMATION:	DEPTH:		
				Fox Hills	251' base	***Deepest water well 300'	
				Sussex	4,152' top		
				Shannon	4,541' top		
				Niobrara	6,892' top		
				J Sand	7,688' top		
				Dakota	7,920' top		
				Lyons	9,051' top		
				Original PA:			
				Well plugged from 443' to 352' w/ 25 sks. 10 sks at surface (60' to 30')			
6,892'		Niobrara Top		Surface pipe capped below plow depth.			
7,688'		J Sand Top					
7,920'		Dakota Top					
9,051'		Lyons Top					
9,164'			7-7/8"	Prepared by:	Chip Eklund		1/29/2019