



## Enerplus Resources

WELL: **Kenneth Thayer 1** FIELD: Wildcat

LOCATION: SWSW Sec 29-T8N-R67E, Weld Co, CO  
660' FSL - 660' FWL

ACCTG CODE: STATUS: DA

ELEVATION: GL - 5,237' API NO 05-123-08834

SPUD DATE: 8/20/1976 COMP DATE: 9/7/1976

MEASURED TD: 9,164' TVD: 9,164'

SURF CSG: 8-5/8" 24# set at 415'.  
Cmtd with 330 sks.

PROD CSG: N/A 7-7/8" open hole to 9,164'

FORMATION: DEPTH:

Fox Hills	251'	base	***Deepest water well 300'
Sussex	4,152'	top	
Shannon	4,541'	top	
Niobrara	6,892'	top	
J Sand	7,688'	top	
Dakota	7,920'	top	
Lyons	9,051'	top	

Original PA:  
Well plugged from 600' to 375' w/ 100 sks.  
10 sks at surface.  
Surface pipe capped below plow depth.

Proposed Re-Entry PA:  
40 sk balanced plug across top of J Sand  
40 sk balanced plug across top of Niobrara  
Cement plug from 465' to surface.

Prepared by: Chip Eklund

1/29/2019