



## Partner Summary Report

Date: 4/11/2018

Report #: 2

Well Name: HEPPBERGER 11-24

DOL:

Spud Date: 2/18/1993

### Well Header

Well Name HEPPBERGER 11-24	API 05-123-16756	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (ftKB) ORIGINAL HOLE - 7,008.4		
Spud Date 2/18/1993	TD Date 2/23/1993	Rig Release Date 2/23/1993	First Gas Sales				
Actual Latitude (°) 40.38249750	Actual Longitude (°) -104.61344650	Quarter 3 NE	Quarter 4 SW	Section 24	Township 5	Township N/S Dir N	Range E/W Dir W

Job: ABANDON , Job Start Date: 4/10/2018 13:00

Objective P&A			AFE Number
Report Start Date 4/11/2018 06:00	Report End Date 4/11/2018 18:00	Operations Summary CREW TO LOCATION. HELD SAFETY MTG. CHECK PRESSURE. 1000/1000, 0 SFC. VERIFY 5K WH WITH 5K 2" CSG VALVES. BULLHEAD TO KILL WELL. CIRC TO TANK 1 HR. 0 PSI CSG/TBG. ND WH, NU & TEST BOPE. UNLAND TBG, TOOH LD 11 JTS 2 3/8 TBG TO TRAILER, SB 208 JTS. MIRU SPN WL. HELD SAFETY MTG. PU CIBP AND SETTING TOOL. RIH SET CIBP @ 6500' KB. POOH LD TOOLS. RDMO WL. SECURE WELL SDFN.	



## Partner Summary Report

Date: 4/12/2018

Report #: 3

Well Name: HEPPBERGER 11-24

DOL:

Spud Date: 2/18/1993

### Well Header

Well Name HEPPBERGER 11-24	API 05-123-16756	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (ftKB) ORIGINAL HOLE - 7,008.4		
Spud Date 2/18/1993	TD Date 2/23/1993	Rig Release Date 2/23/1993	First Gas Sales				
Actual Latitude (°) 40.38249750	Actual Longitude (°) -104.61344650	Quarter 3 NE	Quarter 4 SW	Section 24	Township 5	Township N/S Dir N	Range E/W Dir W

Job: ABANDON , Job Start Date: 4/10/2018 13:00

Objective P&A			AFE Number
Report Start Date 4/12/2018 06:00	Report End Date 4/12/2018 18:00	Operations Summary CREW TO LOCATION. HELD SAFETY MTG. TIH 208 JTS 2 3/8 TBG. TAG CIBP @ 6483' MD. CIRC WELL, TEST CIBP TO 1000 PSI/15 MIN. GOOD TEST. MIRU SPN CEMENTERS. HELD SAFETY MTG. MIX/PUMP 20 SX G NEAT CEMENT ON CIBP. ETOC 6236'. CLEAN UP CEMENT EQUIP, RDMO. TOOH LD 31 JTS 2 3/8 TBG. LAND BTG @5491' KB. CIRC 2 BTMS UP. LAND TBG @ 5491' KB. ND BOPE, NU WH. SECURE WELL, RDMO LEED 734.	