

**TUDEX PETROLEUM INC**  
**Freeman 13-2**

Op. #90615 LOCATION ID 336189  
**API #123-13486**

Prepared mjh

2/28/2019

COGCC Document No. 0

**FIELD NAME**  
**FIELD NUMBER**

**SPINDLE**  
**77900**

Notes:

LOCATION

**Basin** DENVER - JULESBURG  
**Location** SESW 13 T2N R67W  
**Elevation** 4890

Depth

Formation/Member

Existing Casing and Cement Coverage

Depth

Plug Placement

0

0

500

500

1,000

1,000

1,500

1,500

2,000

2,000

2,500

2,500

3,000

3,000

3,500

3,500

4,000

4,000

4,500

4,500

SUSSEX 4,460'-4568'  
 2.375" tubing set at 4,444'

8-5/8", 24 ppf Surface Casing, Set at 480'  
 cemented w/ 350 sx in 12-1/4" hole

SB5=547'  
 Deepest DWR w/in 1 mi.=540'

Production Perfs @ 4,486'-4527'  
 4,651' Prod. Casing, 4-1/2", 11.6 ppf  
 Cemented with 130 sx in 7.875" hole

Cut 4-1/2" casing at  
 600' 200 sx stub plug  
 from 650' to surface

100' Perf and  
 squeeze at 2500'  
 25 sx through and 7  
 sx bal. plug inside

CBL Required from  
 top of bridge plug to  
 surface.

CIBP w/ 2 sx @4,411'  
 (75' above top perf.)