

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401904968

Receive Date:

Report taken by:

## Site Investigation and Remediation Workplan (Initial Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

### OPERATOR INFORMATION

Name of Operator: BP AMERICA PRODUCTION COMPANY	Operator No: 10000	<b>Phone Numbers</b>
Address: 380 AIRPORT RD		
City: DURANGO	State: CO Zip: 81303	
Contact Person: Steve Moskal	Email: steven.moskal@bpx.com	
		Phone: (505) 330-9179
		Mobile: (505) 330-9179

### PROJECT, PURPOSE & SITE INFORMATION

#### PROJECT INFORMATION

Remediation Project #: \_\_\_\_\_ Initial Form 27 Document #: 401904968

#### PURPOSE INFORMATION

- |  |  |
|--|--|
| <input type="checkbox"/> 901.e. Sensitive Area Determination                                       | <input type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water                   |
| <input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure                             | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation                 | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project                                  |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste                      | <input type="checkbox"/> Rule 906.c.: Director request   |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input type="checkbox"/> Other _____   |

#### SITE INFORMATION

N Multiple Facilities ( in accordance with Rule 909.c. )

Facility Type: SPILL OR RELEASE	Facility ID: 458834	API #: _____	County Name: LA PLATA
Facility Name: Thomas Jacquez E1 PW Line		Latitude: 37.103723	Longitude: -107.897424
		** correct Lat/Long if needed: Latitude: _____	Longitude: _____
QtrQtr: NESE	Sec: 14	Twp: 33N	Range: 10W Meridian: N Sensitive Area? Yes

#### SITE CONDITIONS

General soil type - USCS Classifications SM Most Sensitive Adjacent Land Use Irrigation canal

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

#### Other Potential Receptors within 1/4 mile

Animas River, Citizen's Animas Ditch

# SITE INVESTIGATION PLAN

## TYPE OF WASTE:

☒ E&P Waste

☐ Other E&P Waste

☒ Non-E&P Waste

☒ Produced Water

☐ Workover Fluids

Chemical injection

☒ Oil

☐ Tank Bottoms

☒ Condensate

☐ Pigging Waste

☐ Drilling Fluids

☐ Rig Wash

☐ Drill Cuttings

☐ Spent Filters

☐ Pit Bottoms

☐ Other (as described by EPA)

## DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	SOILS	380'x45'x1'deep	Physically measure and delineated via excavation
Yes	SURFACE WATER	3.6 miles	Visible sheen on Animas Ditch

## INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

The water transference line was shut in and isolated. Booms were deployed along the Animas Ditch and High Flume Creek to collect light sheen. These booms were continuously monitored and changed daily. The water transfer line was excavated and impacted soils surrounding the release point were removed and transported off site for disposal. Fresh water was provided to livestock relying on the irrigation water as a drinking source.

## PROPOSED SAMPLING PLAN

### Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? ( Number, type (grab/composite), analyses, and locations of samples ):

Soil samples collected from the release point excavation area were composite samples. Composite samples collected from each sidewall and base of the excavation to be representative of the area. Failed samples were further excavated to meet cleanup criteria. The water to the Animas Ditch was shut off during the excavation activities to reduce risk of further impact and to ease crossing of the ditch.

Sampling of the ditch will be conducted pending agreement of access provided by the Citizens Animas Ditch board. BP has proposed to collect samples from various location of the ditch, from each property parcel or every quarter mile, whichever is more frequent. At each sample location, one, three point, composite sample would be collected from the upper ditch bank where water was flowing during the release and is identified as a potential impact zone. Similarly, at each sample point, one, three point, composite sample would be collected from the base of the canal. These samples would be

### Proposed Groundwater Sampling

☐ Will groundwater samples be collected as part of this investigation? ( Number, analyses, and locations of samples ):

Groundwater samples collected from nearby domestic water wells as a precautionary measure. No significant threat to groundwater associated with the release.

### Proposed Surface Water Sampling

☒ Will surface water samples be collected as part of this investigation? ( Number, analyses, and locations of samples ):

Water samples were collected along the Animas Ditch and High Flume Creek. Attached are the sample locations. Once water is returned to the ditch, water samples will be collected to ensure there is no impact above regulatory limit.

## Additional Investigative Actions

☒ Additional alternative investigative actions described in attached Site Investigation Plan ( summary ):

The area of impact along the Animas Ditch banks and High Flume Creek were sprayed with a biodegradable surfactant to promote hydrocarbon degradation. The proposed sampling of the ditch will determine where and if any remedial action is required. Once access is granted, BP will perform sampling. Results will be shared to determine remedial action.

# SITE INVESTIGATION REPORT

## SAMPLE SUMMARY

### Soil

Number of soil samples collected 45

Number of soil samples exceeding 910-1 3

Was the areal and vertical extent of soil contamination delineated? Yes

Approximate areal extent (square feet) 950

### NA / ND

-- Highest concentration of TPH (mg/kg) 1844.3

-- Highest concentration of SAR 14.5

BTEX > 910-1 No

Vertical Extent > 910-1 (in feet) 3

### Groundwater

Number of groundwater samples collected 5

Was extent of groundwater contaminated delineated? No

Depth to groundwater (below ground surface, in feet) 15

Number of groundwater monitoring wells installed 0

Number of groundwater samples exceeding 910-1 0

-- Highest concentration of Benzene (µg/l) 5E-05

-- Highest concentration of Toluene (µg/l) 5E-06

NA Highest concentration of Ethylbenzene (µg/l)

NA Highest concentration of Xylene (µg/l)

NA Highest concentration of Methane (mg/l)

### Surface Water

28 Number of surface water samples collected

0 Number of surface water samples exceeding 910-1

If surface water is impacted, other agency notification may be required.

## OTHER INVESTIGATION INFORMATION

☒ Were impacts to adjacent property or offsite impacts identified?

Surface water impacts to Animas Ditch. No water quality exceeded COGCC Standards. Domestic water wells sampled as groundwater indicate one well has elevated benzene and toluene, but is not related to this release. BP will investigate to determine if well is influenced by production wells in the area.

☒ Were background samples collected as part of this site investigation?

Upstream water sample from the Animas Ditch and background soil samples. Background soil samples were also collected during the excavation activities.

☒ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) 282

Volume of liquid waste (barrels) 0

☒ Is further site investigation required?

BP has proposed to collect samples from various location of the ditch, from each property parcel or every quarter mile, whichever is more frequent. At each sample location, one, three point, composite sample would be collected from the upper ditch bank where water was flowing during the release and is identified as a potential impact zone. Similarly, at each sample point, one, three point, composite sample would be collected from the base of the canal. These samples would be submitted for laboratory analysis of TPH and volatile organics.

Follow up sampling, following the return of water to the Animas Ditch, to determine if further action is required.

# REMEDIAL ACTION PLAN

## SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

The area of soil contamination was excavated and confirmed below standard with confirmation sampling. The residual impacts along the Animas Ditch bank and High Flume Creek have been sprayed with a biodegradable surfactant the proposed sampling plan will determine the effectiveness of the application and will also determine if and where remedial activities are required.

## REMEDICATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Soil remediation at the release point has been completed and confirmed no further action is necessary. BP proposed sampling of the irrigation canal will determine if and where remedial actions will be required. The results of the proposed sampling plan will be analyzed and shared to determine the remedial course of action if necessary.

The sampling of the canal is contingent on an access agreement to be approved by the Citizens Animas Ditch company.

## Soil Remediation Summary

☒ In Situ

\_\_\_\_\_ Bioremediation ( or enhanced bioremediation )

\_\_\_\_\_ Chemical oxidation

\_\_\_\_\_ Air sparge / Soil vapor extraction

\_\_\_\_\_ Natural Attenuation

Yes Other Promoted hydrocarbon  
degradation via application of  
biodegradable surfactant.  
\_\_\_\_\_

☒ Ex Situ

Yes Excavate and offsite disposal

\_\_\_\_\_ If Yes: Estimated Volume (Cubic Yards) 282

\_\_\_\_\_ Name of Licensed Disposal Facility or COGCC Facility ID # \_\_\_\_\_

\_\_\_\_\_ Excavate and onsite remediation

\_\_\_\_\_ Land Treatment

\_\_\_\_\_ Bioremediation (or enhanced bioremediation)

\_\_\_\_\_ Chemical oxidation

\_\_\_\_\_ Other \_\_\_\_\_

## Groundwater Remediation Summary

☐ Bioremediation ( or enhanced bioremediation )

☐ Chemical oxidation

☐ Air sparge / Soil vapor extraction

☐ Natural Attenuation

☐ Other \_\_\_\_\_

## GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

## REMEDATION PROGRESS UPDATE

### PERIODIC REPORTING

**Frequency:** ☐ Quarterly ☒ Semi-Annually ☐ Annually ☐ Other \_\_\_\_\_

**Report Type:** ☐ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report

☒ Other Vegetation monitoring \_\_\_\_\_

### WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes \_\_\_\_\_

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Impacted soil

Volume of E&P Waste (solid) in cubic yards \_\_\_\_\_ 252

E&P waste (solid) description \_\_\_\_\_ Impacted soils

COGCC Disposal Facility ID #, if applicable: \_\_\_\_\_

Non-COGCC Disposal Facility: Envirotech Landfarm \_\_\_\_\_

Volume of E&P Waste (liquid) in barrels \_\_\_\_\_ 0

E&P waste (liquid) description \_\_\_\_\_

COGCC Disposal Facility ID #, if applicable: \_\_\_\_\_

Non-COGCC Disposal Facility: \_\_\_\_\_

## RECLAMATION PLAN

### RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The area of the water transfer line has been reclaimed. The area was contoured to pre-spill conditions, with the addition of water bars. The slope of the hillside was stabilized with matting and hydroseeded with a like and kind seed mix to mimic surrounding conditions. The area will be monitored to determine seed success and for weed infestation on a bi-annual frequency.

Is the described reclamation complete? Yes \_\_\_\_\_

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☒ Interim? ☐ Final?

Did the Surface Owner approve the seed mix? Yes \_\_\_\_\_

If NO, does the seed mix comply with local soil conservation district recommendations? Yes \_\_\_\_\_

## IMPLEMENTATION SCHEDULE

### PRIOR DATES

Date of Surface Owner notification/consultation, if required. \_\_\_\_\_ 11/16/2018

Actual Spill or Release date, if known. \_\_\_\_\_ 11/03/2018

### SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). \_\_\_\_\_ 11/06/2018

Date of commencement of Site Investigation. \_\_\_\_\_ 11/06/2018

Date of completion of Site Investigation. \_\_\_\_\_

### REMEDIAL ACTION DATES

Date of commencement of Remediation. \_\_\_\_\_ 11/12/2018

Date of completion of Remediation. \_\_\_\_\_

### SITE RECLAMATION DATES

Date of commencement of Reclamation. \_\_\_\_\_ 12/12/2018

Date of completion of Reclamation. \_\_\_\_\_

**OPERATOR COMMENT**

BP has proposed the enclosed comprehensive sampling plan to determine if and where remedial action will be required along the Citizens Animas Ditch. Implementaion and scheduling of this plan is contingent on the approval of an access agreement bewteen the Citizens Animas Ditch Company and BP.

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: ` Steve Moskal \_\_\_\_\_

Title: Enviro Coord \_\_\_\_\_

Submit Date: ` \_\_\_\_\_

Email: steven.moskal@bpx.com \_\_\_\_\_

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Date: \_\_\_\_\_

Remediation Project Number: \_\_\_\_\_

**COA Type****Description**

	Prior to implementing the plans detailed in this report, the operator shall collect soil samples documenting the effectiveness of remediation efforts performed to date. Without this additional investigation the plan to flush the impacted ditch is not approved or an acceptable plan. Samples shall be collected, at a minimum, at the following locations: near the inlet to the High Flume Canyon siphon, near the confluence of the siphon bypass and High Flume Creek, downstream of the box culvert underneath the county road, and at the High Flume Canyon siphon outlet. Flushing E and P waste downstream, ultimately into the Animas River, is not approved.
--	---

**Attachment Check List**

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

**Att Doc Num****Name**

401905465	ANALYTICAL RESULTS
401905467	SITE MAP
401905479	SITE MAP
401905486	SITE MAP
401905506	SITE MAP
401905528	ANALYTICAL RESULTS
401905531	ANALYTICAL RESULTS
401956370	SOIL SAMPLE LOCATION MAP
401956372	DISPOSAL MANIFESTS
401956373	DISPOSAL MANIFESTS

Total Attach: 10 Files

**General Comments****User Group****Comment****Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)