

Ranger Energy Services, LLC  
 800 Gessner, Suite 1000  
 Houston, TX 77024  
 (713) 935-8900  
 (713) 935-8901 (FAX)



183816

Rig # R5011

### Cement Ticket

<b>Customer Name</b>	<b>Date Of Service:</b>
Bonanza Creek Energy Inc.	1/25/2019

<b>Location</b>	<b>Equipment</b>
Wetco Farms 12-4-J	C1003

Billing			
Description	Qty	Rate	Total
P and A Charge(Each)	1.00 @		
Mileage(Miles)	40.00 @		
G Cement(Bags)	100.00 @		
Data Acquisition(Each)	1.00 @		
Iron Inspection(Each)	1.00 @		
Sugar(Lbs)	50.00 @		
Water Delivery(Barrels)	80.00 @		
Description	Qty		
Miscellaneous	6.00 @		
		water delivery	
		<b>Discount:</b>	\$0.00 (0.00%)
<b>TOTAL BILLABLE AMOUNT</b>			

<b>Description of Work</b>	<b>Start Time</b> 06:00 am	<b>Stop Time</b> 05:00 pm
----------------------------	----------------------------	---------------------------

Drove to Location, Sign JSA, Spott in & RU Equipment, THI w/ 2 3/8" TBG to Pump Balance Plug @ 6200' Held Safety meeting with rig crew, Pressure test Hard line @ 1000 PSI, Establish Circulation w/ water, Mix and Pump 25 sxs of 15.8 # CGC, ( Verify by mud scale, 5.12 bbl of slurry) Displaced w/ 22.71 bbl of water, 2) Hook our Hose to 4.5" CSG, ( Holes was @ 2500' inside 4.5" CSG) Got injection Rate w/ water, Mix and Pump 75 sxs of 15.8 # CGC, ( Verify by mud scale, 15.36 bbl of slurry) Displaced w/ 35 bbl of water, Down 4.5" CSG, Wash & RD Equipment, Drove Back to the Yard

Payroll Section					
Employee		Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total
Supervisor	Jaime, Gustavo	0.00	0.00	0.00	0.00
Operator	Jones, Austin	11.00	0.00	0.00	11.00
Derrick	Gurule, James	11.00	0.00	0.00	11.00
FloorHand	Banuelos Serrano, Cristian	11.00	0.00	0.00	11.00

No UnReported Incidents Per My Signature

Ranger Tool Pusher

Customer/Agent:

Ranger Energy Services, LLC  
 800 Gessner, Suite 1000  
 Houston, TX 77024  
 (713) 935-8900  
 (713) 935-8901 (FAX)



184650

Rig # R5011

### Cement Ticket

<b>Customer Name</b>	<b>Date Of Service:</b>
Bonanza Creek Energy Inc.	1/29/2019

<b>Location</b>	<b>Equipment</b>
Wetco Farm No 12-4-J	C1002

Billing			
Description	Qty	Rate	Total
P and A Charge(Each)	1.00 @		
Mileage(Miles)	40.00 @		
G Cement(Bags)	263.00		
Data Acquisition(Each)	1.00 @		
Iron Inspection(Each)	1.00 @		
Sugar(Lbs)	50.00 @		
Water Delivery(Barrels)	80.00 @		
<b>Description</b>	<b>Qty</b>		
Miscellaneous	5.00 @		
		water delivery	
			<b>Discount: \$0.00 (0.00%)</b>
			<b>TOTAL BILLABLE AMOUNT</b>

<b>Description of Work</b>	<b>Start Time</b> 06:00 am	<b>Stop Time</b> 01:00 pm
----------------------------	----------------------------	---------------------------

Drove to Location, Sign JSA, Spott in & RU Equipment, tih W/ 2 3/8" tbg to Pump Surface Plug @ 864' ( 4.5" CSG was cut @ 750') Held Safety meeting with rig crew, Pressure test Hard line @ 1000 PSI, Establish Circulation w/ water, Mix and Pump 263 sxs of 15.8 # CGC, ( Verify by mud scale, 53 bbl of slurry) TOOHD LD TBG, ND BOP'S, Top off well with cement to Surface, Drove back to the Yard

Payroll Section					
Employee		Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total
Supervisor	Jaime, Gustavo	0.00	0.00	0.00	0.00
Operator	Garcia, Roger	7.00	0.00	0.00	7.00
Derrick	Cisneros, Hector	7.00	0.00	0.00	7.00
FloorHand	Verduzco, Gilberto	7.00	0.00	0.00	7.00
FloorHand	Casillas, Allen Jonathan	7.00	0.00	0.00	7.00

No UnReported Incidents Per My Signature

Ranger Tool Pusher

Customer/Agent: