

Cementer's Well Service, Inc.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

SRC Energy - Surface Cement Data Sheet



CEMENTER'S
—WELL SERVICE, INC.—

9/27/2018	Well Owner: SRC Energy		Well No.	40N-8B-L	
County	WELD	State	CO	Lease	Bost Farm
Client					
SRC Energy					
Address					
1625 Broadway					
City		Denver	State	CO	80202
Type of Job	Surface	Depth	1820 ft.	Time On	330
	Surface	9 5/8 csg 36# 13 1/2 Hole	Bottom of Surface	1810 ft.	Plug Down
		Plug Landed @	1779 ft.		600
		Pipe Landed @	1810 ft.		
Other:					
Description		Quantity	Meas.		
Data Acquisition	* see attached graph and data	1			
Cement Neat		718	SKS		
Calcium Chloride		1.5	%		
Gel		3	%		
Mileage Heavy		40	Miles		
Mileage Pick-Up		20	Miles		
Mud Flush		1			
Additional Cement			SKS		
Mixing Rate	4 bpm				
Disp. Rate	5 bpm				
Slurry Vol.	1.61 cuft3/sk				
Slurry Wt.	13.9 ppg				
Water/Cement	8.2 gal/sk				
Water Temp.	55				
Total Slurry Vol.	205.9	BBLs Cement			
Landed Plug @	1500	PSI / Final Lift @	600	PSI	
Pre-Flush W/	10 fresh 20 flush	BBLs H ² O			
Displace W/	136.7	BBLs H ² O			
Circulate	17	BBLs Cement			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming
1202		Pump Truck		20	
104/1214		Bulk Truck		20/20	
					Total Mileage

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By _____

Received By _____

Customer or His Agent