

Rothe 22-6
Current WBD

1985 FNL1995 FWL SENW 6 4N 63W 6th PM
Lat 40.34325 Long -104.48239
Weld County, Colorado
API #05-123-26161

Spud date 8/13/2007

4605 KB
4595 GL

8.625", 24#/ft Wt, Grade, 662', 12.25" hole
Cemented to surface w/ 410 sx.

TOC 2950'

Niobrara 6364'
6366' - 6514'

Codell 6625'
Perfs 6624' - 6638'

4 1/2", 11.6#/ft, Grade, 6784', 7 7/8" hole
Cemented with 243 sxs

PBTD 6782 ft
TD 6810 ft 8/19/1986

Updated 2/28/2019 rcs