

DOW 41-33

Current WBD

830 FNL652 FEL NENE 33 5N 63W 6th PM

Lat 40.36094 Long -104.43375

Weld County, Colorado

API #05-123-21329

Spud date 9/28/2003

4542 KB

4532 GL

8.625", 24#/ft Wt, Grade, 410', 12.25" hole
Cemented to surface w/ 285 sx.

TOC 5910'

CIBP w/ 2sx cement @ 6212"

11/12/2018

Niobrara 6212
Perfs 6295' - 6355'

Codell 6456
Perfs 6459' - 6470'

J Sand 6912
Perfs 6914' - 6980'

CIBP w/ 2sx cement @ 7150'

1/12/2004

Dakota 7156
Perfs 7270' - 7274'

4 1/2", 11.6#/ft, Grade, 7371', 7 7/8" hole
Cemented with 372 sxs

PBTD 7368 ft

TD 7375 ft 10/30/2003

Updated 3/25/2019 rcs