



SRC ENERGY

## AnnFill Wellbore Diagram

Operator: SRC Energy

Operator #: 10311

Well Name: Howard 3-27

Location: WELD

API: 05-123-13811

Legal: NENW 27 6N 64W

### Current

### Proposed

Deepest Water Well (1 mile): 800'

#### Well History

Spud Date: 01/21/1988

Perfs: Niobrara: 6659' - 6768'

Perfs: Codell: 6925' - 6940'

#### Bradenhead History

Date of last test: N/A

Bradenhead pressure: N/A

#### AnnFill Procedure

Pump 240 sxs 1200' to surface

Surface Hole: 12.25"

Surface Casing:

8.625" 24# @ 258'

185 sacks of cement

240 sxs

#### Formations

Fox Hills (Btm)	1088'
Sussex (Top)	4339'
Shannon (Top)	4689'
Niobrara (Top)	6657'
Codell (Top)	6926'

TOC: 6240' CBL

#### Legend

	Existing Cement
	Cement Pumped
	CIBP
	CICR

6659' - 6768'

6925' - 6940'

Production Hole: 7.875"

Production Casing:

4.5" 15.1# @ 7090'

220 sacks of cement

TD: 7090'