

US ROCKIES REGION
Operation Summary Report

Well: FIRESTONE V 20-08D

Spud date: 10/24/2009

Project: COLORADO-WELD-NAD83-UTM13

Site: FIRESTONE V20-08D

Rig name no.: SPN 710/710

Event: CONST- CAP WELL WORK

Start date: 3/5/2019

End date:

Active datum: RKB @4,983.99usft (above Mean Sea Level)

UWI:

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
2/23/2019	-							
3/5/2019	8:30 - 9:30	1.00	MIRU	30	A	P		MIRU SPN 710
	9:30 - 11:30	2.00	WO/REP	30	E	P		RU PUMP HARDLINE. CHECK PRESS TP 700#. CP 250#. SP 0#. BD WELL TO WORK TANK. CONTROL W/90 BW-BIO
	11:30 - 14:00	2.50	WO/REP	30	D	P		RU HOLESEEKERS TESTING. TEST BOP BLINDS ON STUMP TEST FAILED. PULLED RAMS OUT. THAW OUT & CHIPPED ICE OFF BOP INSTALL NEW RUBBERS ON RAMS. RE-TEST BLIND RAMS TO SPECS. GOOD TEST
	14:00 - 15:00	1.00	WO/REP	30	F	P		ND WH TREE. WORK WH MANDREL FREE. NU & TORQ BOP
	15:00 - 15:30	0.50	WO/REP	30	D	P		INSTALL TBG SUB ON WH MANDREL TEST PIPE RAMS TO SPECS. GOOD TEST. RD TEST UNIT
	15:30 - 17:30	2.00	WO/REP	31	I	P		RU HOLESEEKERS EMI UNIT. TOO H WHILE EMI. TOTAL 257 JTS 2-3/8" 4.7# J55, XN NC. (101 YELLOW, 153 BLUE, 3 RED # 75, 250, 257.
	17:30 - 18:00	0.50	WO/REP	30	I	P		DRAIN PUMP. WINTERIZE EQUIP
	18:00 - 18:30	0.50	WO/REP	30	G	P		CREW TRAVEL TO YARD
3/6/2019	6:00 - 7:30	1.50	WO/REP	30	G	P		CREW TRAVEL TO LOC. JSA MEETING
	7:30 - 8:00	0.50	WO/REP	30	M	P		CHECK PRESS. CP 280#. SP 0#. START EQUIP & WARMUP EQUIP
	8:00 - 10:00	2.00	WO/REP	30	E	P		BD WELL TO WORK TANK. CONTROL W/40 BW-BIO.
	10:00 - 13:00	3.00	WO/REP	31	I	P		PU CSG SCRAPER TIH W/254 JTS TO 8000' LD 17 JTS. TOO H LD SCRAPER.
	13:00 - 15:00	2.00	WO/REP	31	I	P		PU 4.5" CTS RBP RIH & SET W/237 JTS @ 7457'KB. JAY OFF RBP LD 1 JT
	15:00 - 16:00	1.00	WO/REP	31	H	P		CIRC GAS OUT. PT CSG TO 1000# HOLD FOR 15 MIN GOOD TEST
	16:00 - 17:00	1.00	WO/REP	31	H	P		TOOH W/ 15 STDs. DUMP 2 SX OF SAND CHASED W/10 BW. TOO H W/15 STDs TO DROP WATER LEVEL @ WH. SWI
	17:00 - 17:30	0.50	WO/REP	30	I	P		DRAIN PUMP. WINTERIZE EQUIP.
	17:30 - 18:00	0.50	WO/REP	30	G	P		CREW TRAVEL TO YARD
3/7/2019	6:00 - 7:00	1.00	WO/REP	30	G	P		CREW TRAVEL TO LOC. JSA MEETING
	7:00 - 8:00	1.00	WO/REP	30	M	P		CHECK PRESS. TP 0# CP 03. SP 0#. START & WARMUP EQUIP
	8:00 - 11:30	3.50	WO/REP	31	I	P		TOOH. PU 4.5" CTS RBP SET @ 7303' KB. JAY OFF RBP LD 2 JTS. LAND W/230 JTS 2-3/8" 4.7# J55 XN, RETREAVING HEAD EOT @ 7250 KB.
	11:30 - 12:30	1.00	WO/REP	42	B	P		RU SWAB EQUIP. BROACH TBG TO XN. RD SWAB EQUIP
	12:30 - 13:00	0.50	WO/REP	31	H	P		DUMP 2 SX SAND DOWN TBG CHASED W/10 BBLs WATER.
	13:00 - 14:00	1.00	WO/REP	30	J	P		ND BOP. NU WH W/DOUBLE FLANGE VALVES.
	14:00 - 14:30	0.50	WO/REP	52	G	P		TORQ & TEST WH TO 5K. OK. RD TESTER.
	14:30 - 15:00	0.50	WO/REP	47	A	P		RD PUMP
	15:00 - 16:00	1.00	WO/REP	30	C	P		RDMO TO FIRESTONE V20-2