

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402002616

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100322

Contact Name: Craig Richardson

Name of Operator: NOBLE ENERGY INC

Phone: (303) 228-4232

Address: 1001 NOBLE ENERGY WAY

Fax:

City: HOUSTON

State: TX

Zip: 77070

API Number 05-123-44473-00

County: WELD

Well Name: Harper

Well Number: A21-674

Location: QtrQtr: NWSW Section: 21 Township: 6N Range: 64W Meridian: 6

Footage at surface: Distance: 2367 feet Direction: FSL Distance: 950 feet Direction: FWL

As Drilled Latitude: 40.470753 As Drilled Longitude: -104.561169

GPS Data:

Date of Measurement: 01/07/2019 PDOP Reading: 3.3 GPS Instrument Operator's Name: Toa Sagapolutele

** If directional footage at Top of Prod. Zone Dist.: 1087 feet. Direction: FNL Dist.: 1221 feet. Direction: FWL

Sec: 21 Twp: 6N Rng: 64W

** If directional footage at Bottom Hole Dist.: 1023 feet. Direction: FNL Dist.: 117 feet. Direction: FEL

Sec: 22 Twp: 6N Rng: 64W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 02/13/2019 Date TD: 02/16/2019 Date Casing Set or D&A: 02/17/2019

Rig Release Date: 02/23/2019 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 16788 TVD** 6854 Plug Back Total Depth MD 16729 TVD** 6854

Elevations GR 4743 KB 4773 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

MWD/LWD, (Neutron in 123-44541)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	36.94	0	110	64	0	110	CALC
SURF	13+1/2	9+5/8	36	0	1,928	675	0	1,928	VISU
1ST	8+1/2	5+1/2	17	0	16,776	1,703	2,442	16,776	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS	371				
PIERRE	510				
PARKMAN	3,723				
SUSSEX	4,307				
SHANNON	5,176				
TEEPEE BUTTES	6,204				
SHARON SPRINGS	7,089				
NIOBRARA	7,136				

Comment:

As drilled GPS was surveyed after conductor was set.

TPZ is estimated, actual TPZ will be submitted on form 5A.

Alternative Logging Exception: No Open Hole Logs ran per rule 317.p Neutron ran on Kona A19-646 (123-44541).

Noble will run the CBL prior to completing (perforating) the well. The CBL will be submitted via Sundry Notice immediately after it is run. The top of cement calculation is based on contractor's cement tickets.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Julie Webb

Title: Sr. Regulatory Analyst

Date: _____

Email: julie.webb@nblenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
402003097	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
402010901	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
402010898	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402010904	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402010906	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402010907	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

