



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

(Indicate nature of data by checking below)

Notice of intention to drill.....
 Notice of intention to change plans.....
 Notice of date for test of water shut-off.....
 Report on result of test of water shut-off.....
 Notice of intention to re-drill or repair well.....
 Notice of intention to clean out well.....
 Statement of shooting.....
 Statement of perforating.....
 Notice to pull or otherwise alter casing..... Setting Casing X.....
 Notice of intention to abandon well.....
 Report of work done on well since previous report.....

November 1 1950

Following is a (~~notice of intention to do work~~) (On land)
 (report of work done) (patented) described as follows:

Colorado	Logan	Merino Prospect
State	County	Field
1	Kilmer	20 SE SW SW
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		6 N. 54 W. 6th
		(Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of South and 990 ft. (E) of West
 Section 20. ~~XXIX~~ ~~XXIX~~

The elevation above sea level is 4251.40 ft. (Ground)

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

The above described well was drilled to a total depth of 5094 on 10-14-50.
 The production string, consisting of 164 joints of 5 1/2" OD, 14#, 8 RT, J-55 casing,
 was landed at 5047.08' (KB) and cemented with 150 sacks of cement by Howco. A Larkin
 Cementrol shoe was run on the bottom of the first joint and the baffle collar was run
 between the first and second joints. Top and bottom plugs were used and the cement
 was in place at 2:30 PM on October 15, 1950.

At the end of 48 hrs., a pressure of 700 psi was applied to the casing for
 one hour. No leakage was noticed so the plug was drilled at 2:30 PM on October 17,
 1950.

Approved: *John E. Brown* 11/1/50
 State Oil Inspector

Company Trigood Oil Company
 Address Box 1689, Casper, Wyoming
 By *J. L. Fusselman*
 Title J. L. Fusselman, Asst. Mgr.

Submit reports of proposed work, for approval, on this form in Duplicate.

J

6