

OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS



00193486

(Indicate nature of data by checking below)

Notice of intention to drill.....X  
Notice of intention to change plans.....  
Notice of date for test of water shut-off.....  
Report on result of test of water shut-off.....  
Notice of intention to re-drill or repair well.....  
Notice of intention to clean out well.....  
Statement of shooting.....  
Statement of perforating.....  
Notice to pull or otherwise alter casing.....  
Notice of intention to abandon well.....  
Report of work done on well since previous report.....

19

Following is a (notice of intention to do work) (~~NOTICE~~)  
(~~REPORT OF WORK DONE~~) (patented) described as follows:

Colorado	Logan	Merino		
State	County	Field		
1	Kilmer	20 SE, SW, SW	6 N.	54 W.
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)	(Twp.)	(Range) (Meridian)

The Well is located 330 ft. (N) of S. line and 990 ft. (E) of W. Line  
(S) (W)

The elevation above sea level is 4251.40 ft. Grd.

Details of Plan of Work: (State names of and expected depths to objective sands:  
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
ing points, and all other important proposed work.)

We propose to drill a well using rotary tools in the Merino Prospect Field on the  
Couch Lease, the well to be known as Kilmer #1. The proposed well will be drilled  
to the Dakota formation.

It is expected that approximately 200 ft. of 10 3/4 inch, 8 Rd. Thd., 32.75 lb.  
casing will be run as the surface string and cemented to the surface.

It is estimated that the Dakota formation will be found at 5100 ft. below the kelly  
bushing. In the event a production string is needed, 5 1/2 inch, 8 Rd. Thd. 14 lb.,  
J-55 casing will be landed at the top of the producing formation and cemented with  
sufficient amount of cement to conform with good engineering practice.

All measurements reported will be from the Kelly Bushing.

Approved: Oct 13 1950  
John E. Linn  
State Oil Inspector

Company TRIGOOD OIL COMPANY

Address Box 1689, CASPER, WYOMING

By J. F. Fushman

Title Asst. Manager

Submit reports of proposed work, for approval, on this form in Duplicate.