

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402028385

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: CRYSTAL MCCLAIN

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 9294398

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-47873-00

County: WELD

Well Name: REESE

Well Number: 21-3HZ

Location: QtrQtr: SWNW Section: 21 Township: 2N Range: 67W Meridian: 6

Footage at surface: Distance: 2065 feet Direction: FNL Distance: 322 feet Direction: FWL

As Drilled Latitude: 40.125499 As Drilled Longitude: -104.903980

GPS Data:

Date of Measurement: 11/14/2018 PDOP Reading: 1.4 GPS Instrument Operator's Name: TRAVIS HOLLAND

** If directional footage at Top of Prod. Zone Dist.: 2485 feet. Direction: FNL Dist.: 752 feet. Direction: FWL

Sec: 21 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 68 feet. Direction: FNL Dist.: 623 feet. Direction: FWL

Sec: 16 Twp: 2N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 11/05/2018 Date TD: 02/25/2019 Date Casing Set or D&A: 02/26/2019

Rig Release Date: 03/07/2019 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 15737 TVD** 7403 Plug Back Total Depth MD 15732 TVD** 7404

Elevations GR 4998 KB 5019 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, MWD/LWD. (GR/RES in API 123-47871).

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	101	64	0	101	VISU
SURF	13+1/2	9+5/8	36	0	1,874	700	0	1,874	VISU
1ST	7+7/8	5+1/2	17	0	15,727	1,480	1,520	15,727	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS	1,164				
PARKMAN	4,306				
SUSSEX	4,716				
SHARON SPRINGS	7,476				
NIOBRARA	7,598				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

Per Rule 317.p Exception, Open Hole Resistivity Logs have been run on the Reese 21-6HZ Well (API 123-47871).

The Top of Productive Zone provided is an estimate based on the landing point at 8048' MD.

Completion is estimated for Q2 2019.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: CRYSTAL MCCLAIN

Title: REGULATORY ANALYST Date: _____ Email: CRYSTAL.MCCLAIN@ANADARKO.COM

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
402028420	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
402028422	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
402028406	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402028409	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402028415	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402028416	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402028423	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

