

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
402034923

Date Received:
05/08/2019

FIR RESOLUTION FORM

Overall Status: CAC

CA Summary:

3 of 3 CAs from the FIR responded to on this Form

3 CA Completed
0 Factual Review Request

OPERATOR INFORMATION

OGCC Operator Number: 10665

Name of Operator: CCRP OPERATING INC

Address: 717 17TH STREET STE 1525

City: DENVER State: CO Zip: 80202

Contact Name and Telephone:

Name: _____

Phone: () _____ Fax: () _____

Email: _____

Additional Operator Contact:

Contact Name

Phone

Email

Sydney Smith

3039104511

ssmith@clearcreekrp.com

COGCC INSPECTION SUMMARY:

FIR Document Number: 697500020

Inspection Date: 04/24/2019

FIR Submit Date: 04/25/2019

FIR Status: _____

Inspected Operator Information:

Company Name: CCRP OPERATING INC

Company Number: 10665

Address: 717 17TH STREET STE 1525

City: DENVER State: CO Zip: 80202

LOCATION - Location ID: 456179

Location Name: True Ranch Fee Number: 2326 East County: _____

Qtrqr: NENE Sec: 23 Twp: 12N Range: 65W Meridian: 6

Latitude: 40.998720 Longitude: -104.623110

FACILITY - API Number: 05-123- -00 Facility ID: 456179

Facility Name: True Ranch Fee Number: 2326 East

Qtrqr: NENE Sec: 23 Twp: 12N Range: 65W Meridian: 6

Latitude: 40.998720 Longitude: -104.623110

CORRECTIVE ACTIONS:

1 CA# 124584

Corrective Action: Comply with Rule 603.f .

Date: 05/09/2019

Response: CA COMPLETED

Date of Completion: 05/08/2019

Operator

Comment:

Operator cleaned location to ensure compliance with Rule 603.f. Operator reviewed Rule 603.f with field team.
Operator re-emphasized company weekly inspection policy to ensure compliance with rule 603.f.

COGCC Decision: _____

COGCC
Representative: _____

2 CA# 124585

Corrective Action: Operator shall implement long-term well pad stabilization to abide by Rule 1002 e.(1), as the location should be in compliance at all times.

Date: 05/09/2019

Operator shall take measures to comply with Rule 1004 and control wind erosion throughout the impacted deposition areas off Location.

Response: CA COMPLETED

Date of Completion: 05/08/2019

Operator
Comment:

Clear Creek re-graded the southeastern area of the True Ranch 23 well pad to establish a berm along the downwind side of the pad. This berm will serve as a barrier from allowing wind blown dust and sand to freely escape location. The berm is approximately 5 ft high. By establishing the berm and pulling back the edge of pad surface, a 6:1 slope was established along the eastern and southern sides of the pad to create a more gradual slope. This will promote more immediate and successful grass growth (i.e. long term stabilization). Prior to spreading stabilization product, the reclaimed area and slopes were surface roughed to allow for hydromulch product to settle into soil depressions for long term effectiveness. A Hydromulch product with a slurry mixture consisting of soil binder, mulch tackifier and perennial seeding mixture was applied as the long term stabilizer.

COGCC Decision: _____

COGCC
Representative: _____

3 CA# 124586

Corrective Action: Install or repair required BMPs per Rule 1002.f. in accordance with good engineering practices.

Date: 05/09/2019

Response: CA COMPLETED

Date of Completion: 05/08/2019

Operator
Comment:

Clear Creek personnel manually removed sediment from ditches: The remedy made in as part of the other corrective action will serve to eliminate sediment buildup in the eastern and southern channels. As for the sediment trap, Clear Creek re-sized it to accommodate a volume of 3600 CF/Acre for a disturbed drainage of 7.3 acres for a total volume of 26,280 CF of storage. The Bottom surface area of the sediment trap was sized at 120 ft by 60' and 4 ft in height.

COGCC Decision: _____

COGCC
Representative: _____

OPERATOR COMMENT AND SUBMITTAL

Comment: _____

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct, and complete.

Print Name: Sydney Smith

Signed: _____

Title: Regulatory Manager

Date: 5/8/2019 9:50:24 AM

ATTACHMENT LIST

View Attachments in Imaged Documents on COGCC website (<http://ogccweblink.state.co.us/>) - Search by Document Number.

| <u>Document Number</u> | <u>Description</u> |
|------------------------|--------------------|
|------------------------|--------------------|

| | |
|-----------|-------------------|
| 402035926 | Location Pictures |
|-----------|-------------------|

Total Attach: 1 Files