

FORM

21

Rev
08/14

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401844424

Date Received:

MECHANICAL INTEGRITY TEST

1. Duration of the pressure test must be a minimum of 15 minutes.
2. An original pressure chart must accompany this report if this test was not witnessed by an OGCC representative.
3. For production wells, test pressures must be at a minimum of 300 psig.
4. New injection wells must be tested to maximum requested injection pressure.
5. For injection wells, test pressures must be at least 300 psig or average injection pressure, whichever is greater.
6. A minimum 300 psi differential pressure must be maintained between the tubing and tubing/casing annulus pressure.
7. Do not use this form if submitting under provisions of Rule 326.a(1)B. or C.
8. Written OGCC notification must be provided 10 days prior to the test via Form 42, Field Operations Notice
9. Packers or bridge plugs, etc., must be set within 100 feet of the perforated interval to be considered a valid test.

Complete the Attachment

Checklist

OP OGCC

OGCC Operator Number: 10112	Contact Name: Alyssa Beard	Pressure Chart		
Name of Operator: FOUNDATION ENERGY MANAGEMENT LLC	Phone: (303) 244-8114	Cement Bond Log		
Address: 5057 KELLER SPRINGS RD STE 650		Tracer Survey		
City: ADDISON State: TX Zip: 75001 Email: abeard@foundationenergy.com		Temperature Survey		
API Number: 05-123-20232	OGCC Facility ID Number: 258928	Inspection Number		
Well/Facility Name: FEDERAL ALBATROSS	Well/Facility Number: 33-12			
Location QtrQtr: NWSW Section: 33 Township: 8N Range: 60W Meridian: 6				

☒ SHUT-IN PRODUCTION WELL ☐ INJECTION WELL Last MIT Date: _____

Test Type:

☒ Test to Maintain SI/TA status ☐ 5-Year UIC ☐ Reset Packer

☐ Verification of Repairs ☐ Annual UIC TEST

☐ Describe Repairs or Other Well Activities: _____

Wellbore Data at Time of Test				Casing Test Use when perforations or open hole is isolated by bridge plug or cement plug; use if cased-hole only with plug back total depth. Bridge Plug or Cement Plug Depth <div style="border: 1px solid black; width: 100px; height: 20px;"></div>
Injection Producing Zone(s)	Perforated Interval	Open Hole Interval		
DSND	6954-6964			
Tubing Casing/Annulus Test				
Tubing Size:	Tubing Depth:	Top Packer Depth:	Multiple Packers?	
0.375	6896	6896	<input type="checkbox"/>	

Test Data (Use -1 for a vacuum)

Test Date	Well Status During Test	Casing Pressure Before Test	Initial Tubing Pressure	Final Tubing Pressure
11-15-2018	SHUT -IN	-1	-1	-1
Casing Pressure Start Test	Casing Pressure - 5 Min.	Casing Pressure - 10 Min.	Casing Pressure Final Test	Pressure Loss or Gain
400	400	400	400	0

Test Witnessed by State Representative? ☐ OGCC Field Representative _____

OPERATOR COMMENTS:

MIT completed 11-15-18

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Alyssa Beard

Title: HSE/Regulatory Tech Email: regulatory@foundationenergy.com Date: _____

Based on the information provided herein, this Notice (Form 21) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY:

Attachment Check List

Att Doc Num**Name**

401992556	PRESSURE CHART
401992558	OTHER
402041279	FORM 21 ORIGINAL

Total Attach: 3 Files

General Comments

User Group**Comment****Comment Date**

Engineer	Returned to draft. Original Form 21 is missing.	04/26/2019
Engineer	Returned to draft. No Form 42(MIT)(Should be doc#401820789) or INSP in the Related Forms tab. Pressure Chart and Original Form 21 are missing.	11/28/2018

Total: 2 comment(s)