

FORM  
6Rev  
05/18

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401707511

Date Received:

07/19/2018

## WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 10633

Contact Name: Renee Kendrick

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

Phone: (303) 309-1931

Address: 1801 CALIFORNIA STREET #2500

Fax:

City: DENVER State: CO Zip: 80202

Email: renee.kendrick@crestonepr.com

For "Intent" 24 hour notice required,

Name: \_\_\_\_\_ Tel: \_\_\_\_\_

COGCC contact:

Email: \_\_\_\_\_

API Number 05-123-32566-00

Well Name: JILLSON

Well Number: 4-6-22

Location: QtrQtr: SESW Section: 22 Township: 2N Range: 68W Meridian: 6

County: WELD

Federal, Indian or State Lease Number: \_\_\_\_\_

Field Name: WATTENBERG

Field Number: 90750

☐ Notice of Intent to Abandon☒ Subsequent Report of Abandonment

## Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.119537

Longitude: -104.992766

GPS Data:

Date of Measurement: 01/05/2012 PDOP Reading: 2.7 GPS Instrument Operator's Name: PAT LINDERHOLM

Reason for Abandonment: ☐ Dry ☐ Production Sub-economic ☐ Mechanical Problems☐ Other \_\_\_\_\_Casing to be pulled: ☐ Yes ☐ No Estimated Depth: \_\_\_\_\_Fish in Hole: ☐ Yes ☐ No If yes, explain details belowWellbore has Uncemented Casing leaks: ☐ Yes ☐ No If yes, explain details below

Details: \_\_\_\_\_

## Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7704	7720	06/26/2018	B PLUG CEMENT TOP	7400
NIOBRARA	7484	7500	06/26/2018	B PLUG CEMENT TOP	7400
J SAND	8140	8162	06/26/2018	B PLUG CEMENT TOP	8075

Total: 3 zone(s)

## Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	755	300	755	0	VISU
1ST	7+7/8	4+1/2	11.6	8,241	700	8,241	3,526	CBL

## Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 8075 with 2 sacks cmt on top. CIBP #2: Depth 7400 with 2 sacks cmt on top.  
CIBP #3: Depth 600 with 5 sacks cmt on top. CIBP #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set <u>15</u> sks cmt from <u>4541</u> ft. to <u>4347</u> ft.	Plug Type: <u>CASING</u>	Plug Tagged: <input type="checkbox"/>
Set <u>75</u> sks cmt from <u>1500</u> ft. to <u>1245</u> ft.	Plug Type: <u>OPEN HOLE</u>	Plug Tagged: <input type="checkbox"/>
Set <u>40</u> sks cmt from <u>340</u> ft. to <u>212</u> ft.	Plug Type: <u>CASING</u>	Plug Tagged: <input type="checkbox"/>
Set <u>27</u> sks cmt from <u>60</u> ft. to <u>0</u> ft.	Plug Type: <u>CASING</u>	Plug Tagged: <input type="checkbox"/>
Set _____ sks cmt from _____ ft. to _____ ft.	Plug Type: _____	Plug Tagged: <input type="checkbox"/>

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 50 sacks half in. half out surface casing from 820 ft. to 685 ft. Plug Tagged: ☒

Set \_\_\_\_\_ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set \_\_\_\_\_ sacks in rat hole Set \_\_\_\_\_ sacks in mouse hole

### Additional Plugging Information for Subsequent Report Only

Casing Recovered: 1500 ft. of 4+1/2 inch casing Plugging Date: 07/02/2018

\*Wireline Contractor: Cutters

\*Cementing Contractor: Basic Energy

Type of Cement and Additives Used: Class G

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☒ No

\*ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Renee Kendrick

Title: Regulatory Coordinator Date: 7/19/2018 Email: renee.kendrick@crestonepr.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: McFarland, Nick Date: 5/14/2019

### CONDITIONS OF APPROVAL, IF ANY:

COA Type	Description
----------	-------------

--	--

### Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
1801821	OPERATIONS SUMMARY
401707511	FORM 6 SUBSEQUENT SUBMITTED
401707581	WELLBORE DIAGRAM
401707584	CEMENT JOB SUMMARY
401707596	WIRELINER JOB SUMMARY

Total Attach: 5 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Form 7 status set to PA. Form 42 for flowline abandonment filed. Bradenhead test performed and form 17 submitted per COA. No sample required based on results. Form 42 for 48 hour ops notice filed per COA. Well path as drilled in GIS and GPS location accurate per maps. Zones and Casing History consistent with approved intent. WBD, plugging procedure and service tickets consistent.	04/09/2019

Total: 1 comment(s)