




**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Cities Service Oil Co. Field _____ Wildcat X
 Lease Name Kahler "A" Well No. 1 County Baca
 Location SW NE Section 9 Township 35S Range 41-W Meridian _____
 (Quarter Quarter)
3300 feet from South Section line and 3300 feet from West Section Line
~~N or S~~ ~~E or W~~

**BEST COPY
AVAILABLE**

TOTAL DEPTH 4758' DATE OF PLUGGING 4-25-57

DETAILS OF WORK

Set 8-5/8" casing at 1295' drilled to a total depth of 4758'. Ran Induction and Micro log which indicated well to be dry. Filled hole with Heavy rotary drilling mud to 1335; Spot 40 sx cement to 1255; Heavy rotary mud to 70' of surface; 35 sacks cement to 4' of ground level at which point the 8-5/8" casing was cut off and a steel cap welded on the pipe. (No 8-5/8" surface pipe reclaimed).

AWJ	
DVR	
FJR	
OPS	
HHM	
AH	
JED	
FREE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company Cities Service Oil Date 5-7-57

Date MAY 10 1957

Address Box 70, Liberal, Kansas Phone No. MA 4-3893

Director

By H. V. Anderson Title Div. Supt.
 (Signature)

**BEST IMAGE
AVAILABLE**