

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Petroleum, Inc. Field Wildcat X
Lease Name Miller-Gillham Well No. 1 County Logan
Location C NE/4 NE/4 Section 20 Township 10N Range 52W Meridian
(Quarter Quarter)
660' feet from North Section line and 660' feet from East Section Line
Nor S E or W

TOTAL DEPTH 5268' DATE OF PLUGGING 11-28-61

DETAILS OF WORK

Surface Casing - 8 5/8" OD 19.64# set at 188'

Plugged as follows:

Filled hole with heavy mud from 5268' to 4964'. Cemented and displaced through drill pipe 35 sacks cement from 4964' to 4810'. Fill hole with heavy mud from 4810' to 210'. Set second plug 210' to 180' with 10 sacks cement. Fill hole with heavy mud from 180' to 15'. Plugged top of surface with 5 sacks cement from 15' to base of well cellar.

*11/8/62 Loc. Levelled.
Hm*

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: _____ Company Petroleum, Inc. Date 12-7-61
Date DEC - 8 1961 Address 860 Petroleum Club Bldg. Phone No. AC 2-9429
A. J. Gorsia Director By Carl M. Bomholt Title District Landman
(Signature)
Carl M. Bomholt

DEC - 8 1961

Oil and Gas Conservation Commission
OF THE STATE OF COLORADO

PLUGGING RECORD

FORMATION TOPS - ELECTRIC LOG

Niobrara	3958	
Carlile	4340	
Greenhorn	4528	
Bentonite	4726	
"D" Sand	4842	(+ 672)
"J" Sand	4964	(- 794)
"M" Sand	5164	(- 994)
"O" Sand	5211	(-1041)
Total Depth	5272	(5268) Driller)

Drillstem Tests

#1 5026-33 (Log Meas) Open 2 hours, steady weak blow throughout test, recovered 30' muddy water, 775' water. 30 min ISI - 1285#, FP - 65 - 370#, 30 min FSI - 1242. pressure below bottom packer bled to 1800#, IH - 2594, FH-2572.

No Cores.

DATE OF PLUGGING 11-28-61 TOTAL DEPTH 5268

DETAILS OF WORK

Surface casing - 8 1/2" OD 19.0 lb/ft set at 1881
 Plugged as follows:
 Filled hole with heavy mud from 5268' to 5261'. Cemented and displaced through drill pipe 25 sacks cement from 5261' to 5261'. Filled hole with heavy mud from 5261' to 5261'. Set second plug 5261' to 5261' with 10 sacks cement. Filled hole with heavy mud from 5261' to 5261'. Plugged top of surface with 25 sacks cement from 5261' to base of well collar.

ALL
DVR
WRS
HMM
JAM
FBP
JJD
FIC

Approved: _____ Date: _____
 Company: Petroleum, Inc. Date: 11-28-61
 Address: 600 Petroleum Club Building, Denver, Colorado
 By: Carl M. Bonhoff (Signature)
 Title: _____