

Colorado Interstate Gas

LEASE: Flank # 63
FIELD: Flank
COUNTY: Baca
STATE: Colorado
LOCATION: 7 34S 42W
API #: 05-009-06385-00
SPUD DATE: 06/09/83
Rev. Date 05/08/19 - APT

ELEVATION: 3,841' KB: 0
TD: 4,794' GL PBTD: 4,747' GL

TOC @ 558' GL CBL (07/01/83)

Perfs 4,144' – 4,152' GL w/ 2 SPF

PBTD @ 4,747' GL

TD 7-7/8" hole @ 4,794' GL

3 jts 5-1/2" w/ seal assembly
stabbed into receptacle @ 90' GL
2 jts, 9 5/8", 36#, K55, 8R, LT&C
casing 0' – 91' GL swaged to 5-1/2"
csg

3 jts, 13-3/8", 54.5#, K55, 8R, ST&C
csg from 0 – 123' GL swaged to 8-5/8"
csg

TD 17-1/2" Hole @ 150' GL

Cemented surface w/ 750 sxs HLC
and 150 sxs Class H. Cmt Circ.

34 jts, 8-5/8", 24#, K55, ST&C csg from
123' – 1,493' GL

TD 12-1/4" Hole @ 1,500' GL

130 jts, 1 ea. 6', 8' & 10' subs, 2-3/8", 4.7#,
J55, 8R, EUE tbgs. Subs below 1st jt.

Seating Nipple @ 4,107' GL

Baker LOK-Set packer at 4110' GL w/
2,000# comp. wireline entry guide on btm.

Cemented w/ 825 sxs HLC and 200 sxs
50/50 poz. Cmt Circ.

117 jts, 5-1/2", 15.5#, K55, 8R, LT&C
casing set at 4,785' GL