

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



197-12

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating and completing..... XX
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report.....

Following is a ~~(notice of intention to drill or report of work done)~~ August 17 1951
(On land)
(patented) described as follows:

| Colorado | Logan | Mt. Hope | | | |
|------------|-----------------|---------------------|--------|---------|------------|
| State | County | Field | | | |
| 5 | C. F. Green "A" | 25 NE 9N | 5 4 W | 6 PM | |
| (Well No.) | (Lease) | (Sec. and 1/4 Sec.) | (Twp.) | (Range) | (Meridian) |

The well is located 2382 ft. ~~XX~~ of N. line and 1029 ft. ~~XX~~ of
E. line (S) (W)

The elevation above sea level is 4205.85 ft. KB, 4195.85' grd.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)


After drilling firm cement from 4951' to 5015' with 7" OD casing
cemented at 5020', perforations were placed in the casing opposite the
oil bearing sand from 4893' to 4904', with 15/32" bullets. The 2-1/2"
EUE tubing was landed at 5088' KB and swabbing began through the tubing.
After 125 barrels of oil were swabbed from the hole, the well began to
flow. The open flow initial production was gauged at 624 barrels clean
oil per day.

Approved: OCT 11 1951
J. J. Borichak
State Oil Inspector

Company The Texas Company
Address Box 392, Sterling, Colorado
By *E. W. Olson*
Title Production Foreman

Submit reports of proposed work, for approval, on this form in Duplicate.

**COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS**



(Indicate nature of data by checking below)

OIL & GAS
CONSERVATION COMMISSION

Locate Well Correctly

Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

| | | | |
|--|----|--|---|
| | | | |
| | | | |
| | 25 | | 0 |
| | | | |
| | | | |

Notice of intention to dually complete & commingle.

Notice to do work ☒
 Report of work done ☐

Land: Fee and Patented ☒
 State ☐

Lease No. C-2537

COLORADO

State

LOGAN

County

MOUNT HOPE

Field

5

C.F. Green "A"

(Well No.)

(Lease)

NE

25

9N

(1/4 Sec.)

(Sec.)

(Twp.)

54W

(Range)

6th

(Meridian)

The Well is located 347 Ft. (N) of Section Line and 1029 Ft. (E) of East Quarter
 Section Line. (S) x (W) Corner.

The elevation above sea level is 4206 Ft.

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

PURPOSE: To dually complete and commingle "D" and "J" Sand production in the well bore.

This well is currently producing from the "D" Sand through perforations from 4893 to 4904'.

We propose to clean out to PBTD of 5015', perforate the
 "J" Sand in the approximate interval 5002 to 5006', (if necessary,
 sand-oil squeeze the "J" Sand with 5000 gal. crude oil and 5000 pounds
 sand), put well back on production.

| | |
|------|---|
| ASJ | |
| DVR | ✓ |
| FJK | |
| WRS | |
| HHM | |
| AH | |
| JJD | |
| FILE | |

Approved: JUN 14 1956

Date June 13, 1956

Company THE TEXAS COMPANY

P. O. Box 2100

Address Denver 1, Colorado

By J. F. Neill

Title Assistant Division Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.