

RECEIVED
AUG 14 1952

OIL & GAS
CONSERVATION COMMISSION

XX

August 11, 1952

19

colorado

Logan

Mt. Hope

State

County

Field

12

C. F. Green "A"

25

NE $\frac{1}{2}$

9M

51. The

6 PM

The well is located 330 ft.

(S)

of North Line

1014

ft. (E) of

(F)

West Line of NE $\frac{1}{4}$ Sec. 25

to be furnished later

Details of Plan of Work: (State names of and expected depths to objective sands:

We propose to drill a well using rotary tools on the above described well. Approximately 170' of 10-3/4" OD 32.75# H-40 Casing. Casing will be run as surface casing and cemented by an approved method. A 9" hole will then be drilled through the Dakota formation. An electric log will then be run to total depth. If any formation is found to be productive 7" OD 20 & 23# J-55 casing will be run and cemented by an approved method. The casing will then be perforated and the well prepared for producing.

AUG 14 1952

Company The Texas Company

J. J. Zorichak
Director *att*

Address Box 1346 Casper, Wyoming

By Walter Pennell

Title District Superintendent

EGCC TTF WR MME

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.