




00255660

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

308-3

Notice of intention to drill _____ **XX**
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

August 11, 1952

19

Following is a (notice of intention to do work)

(On land)

~~(report of work done)~~

(patented) described as follows:

Colorado

State

Logan

County

Mt Hope

Field

12

(Well No.)

C. F. Green "A"

(Lease)

25(Sec. and $\frac{1}{4}$ Sec.)NE $\frac{1}{4}$ 9N

(Twp.)

54W

(Range)

6PM

(Meridian)

The well is located 330 ft. ~~(NW)~~ of North Line and 1014 ft. (E) of ~~(NW)~~
 (S)

West Line of NE $\frac{1}{4}$ Sec. 25

The elevation above sea level is _____ ft. to be furnished later

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to drill a well using rotary tools on the above described well. Approximately 170' of 10-3/4" OD 32.75# H-40 Casing. Casing will be run as surface casing and cemented by an approved method. A 9" hole will then be drilled through the Dakota formation. An electric log will then be run to total depth. If any formation is found to be productive 7" OD 20 & 23# J-55 casing will be run and cemented by an approved method. The casing will then be perforated and the well prepared for producing.

Approved: AUG 14 1952

J. J. Zorichak
Director *att*

Company The Texas CompanyAddress Box 1346 Casper, WyomingBy Walter R. RasmussenTitle District Superintendent

EGCC TTF WR MME

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.