




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating Dakota "J" Sand XX
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

Locate Well Correctly

		25	

Notice to do work ☒ Land: Fee and Patented ☒
 Report of work done ☐ State ☐ Lease No. _____

Colorado Logan Mount Hope
 State County Field

12 C. F. Green "A" NE 25 9N 54W 6th PM
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 330 Ft. (N) 1014 Ft. (E) of North East
 Qtr. Corner, Sec. 25 (S) (W)
 Section Line.

The elevation above sea level is 4236 KB
4224 GrdFt.

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

The above described well was completed in the Dakota "D" sand on
 2-3-52 with perforations from 4911-22' KB. Initial production was 593
 BOPD. Tests in the Dakota "J" sand before completion in the "D" indic-
 ated good productive potential, and it is desired to open the Dakota
 "J" sand and commingle the "D" & "J" production.

We propose to move in cable tools and clean out the well to 5065'
 (PBTD). The hole will then be loaded with crude oil, Gamma Ray log
 run, and casing perforated at depths corresponding to 5021-24' and
 5043-46' KB on the electric log, 6 Kone shots per foot. The well will
 then be swabbed to stimulate production and then returned to production.

Approved: JUN 19 1956

A. J. Gersin
 Director

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Date June 12, 1956

Company The Texas Company

Address Box 1346, Casper, Wyo.

By Walter Reed

Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.