



Partner Summary Report

Date: 4/17/2019

Report #: 1

Well Name: CONAGRA B30-24

DOL:

Spud Date: 4/22/2009

Well Header

Well Name CONAGRA B30-24	API 05-123-28030	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB) ORIGINAL HOLE - 7,106.8	Current PBTD (ftKB) ORIGINAL HOLE - 7,070.0
Spud Date 4/22/2009	TD Date 4/24/2009	Rig Release Date 4/25/2009		First Gas Sales	
Actual Latitude (*) 40.36663666	Actual Longitude (*) -104.59259584	Quarter 3 NW	Quarter 4 SE	Section 30	Township 5
			Township N/S Dir N	Range E/W Dir W	

Job: ABANDON , Job Start Date: 4/17/2019 06:00

Objective	AFE Number
-----------	------------

Report Start Date 4/17/2019 06:00	Report End Date 4/17/2019 19:00	Operations Summary ROAD RIG TO LOCATION. SPOT IN AND R/U RANGER RIG #5. IWP = 1000/1000#. SURFACE CSG = 0#. BLOW DOWN WELL. CONTROL WELL WITH 80 BBLS FRESH WATER W/BIO. STUMP TEST BOP. TEST/RECORD LOW SIDE @ 250#/5MIN AND HIGH SIDE @ 2500#/5MIN. TEST GOOD. BLEED OFF. N/D WELLHEAD TREE. N/U BOP. TEST/RECORD BOP FLANGE CONNECTION AND HARDLINE. TEST LOW SIDE @ 250#/5MIN AND HIGH SIDE @ 2500#/5MIN. TEST GOOD. BLEED OFF. UN LAND TBG. TOO H S/B IN DERRICK 180 JTS TBG. POOH L/D ON SILLS 43 JTS TBG AND BHA. TOO H FOR TOTAL OF 223 JTS 2 3/8" 4.7# J-55 EUE 8RD TBG. R/U KLX WIRELINE. RIH W/CIBP AND CCL. CORRELATE DEPTHS WITH CBL DATED 5/4/2009. SET CIBP @ 6620.00', (WLM). CONFIRM PLUG SET WITH SETTING TOOL. POOH. MIX 2 SXS QUIKRETE PORTLAND CMT. RIH WITH DUMP BAILER, SPOT TWO SXS CMT ONTO CIBP. POOH. R/D KLX. TIH OUT OF DERRICK WITH NC/XN AND 180 JTS 2 3/8" 4.7# J-55 EUE 8RD TBG. LAND TBG @ +/- 5620.00', (1000.00' ABOVE CIBP). LOAD TBG AND BACKSIDE WITH FRESH WATER. ESTABLISH CIRCULATION. ROLL CLEAN. PRESSURE TEST CIBP @ 1000#, HOLD 15/MIN. TEST GOOD. BLEED OFF. N/D BOP. FLANGE UP WELLHEAD. LOAD TBG AND BACKSIDE. PRESSURE TEST FLANGE CONNECTION @ 1000#, HOLD 15/MIN. TEST GOOD. BLEED OFF. SI WELL. RDMO.
--------------------------------------	------------------------------------	---