

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402082550

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 18600

Contact Name: Anthony Trinko

Name of Operator: COLORADO INTERSTATE GAS COMPANY LLC

Phone: (719) 520-4557

Address: P O BOX 1087

Fax:

City: COLORADO State: CO Zip: 80944

API Number 05-009-05063-00

County: BACA

Well Name: FLANK

Well Number: 2

Location: QtrQtr: SWNW Section: 9 Township: 34S Range: 42W Meridian: 6

Footage at surface: Distance: 1980 feet Direction: FNL Distance: 660 feet Direction: FWL

As Drilled Latitude: 37.099849 As Drilled Longitude: -102.178932

GPS Data:

Date of Measurement: 09/24/2009 PDOP Reading: 2.8 GPS Instrument Operator's Name: G.H. Jarrell

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

Field Name: FLANK

Field Number: 24051

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 09/30/1961 Date TD: 10/16/1961 Date Casing Set or D&A: 10/18/1961

Rig Release Date: 10/18/1961 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☒ Storage ☐ Observation

Total Depth MD 4878 TVD** Plug Back Total Depth MD 4585 TVD**

Elevations GR 3712 KB 0 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

DIL, Sonic, Caliper

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	11	8+5/8	24	0	1,369	550	0	1,369	VISU
1ST	7+7/8	5+1/2	14	0	4,652	250		4,652	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 05/15/1985

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
SQUEEZE	1ST		50	4,014	4,050

Details of work:

05/14/85: Perforated Cherokee squeeze holes from 4,015'-4,016'.
05/15/85: Squeezed with 50 sx. Class H cement.
05/16/85: Ran CEL across squeezed interval.

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
STONE CORRAL		1,406			
NEVA	2,565				
WABAUNSEE	2,852				
TOPEKA	2,888				
LANSING	3,476				
MARMATON	3,806				
CHEROKEE	4,008				
ATOKA	4,244				
MORROW	4,404				
MORROW B	4,504				

Comment:

This Form 5 is being submitted in response to a July 26, 2018 data request for a new Drilling Completion Report for wells that have not had one filed since 1999.

There are no cementing tickets available for this well.

This well is a re-entry of the Kerr-McGee Oil Industries, Inc. Griffith #01 well which was completed as a gas well in October, 1961.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Anthony P. Trinko

Title: Sr. Reservoir Engineer Date: _____ Email: anthony_trinko@kindermorgan.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
	CMT Summary *	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
402082663	TIF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
402082827	WELLBORE DIAGRAM	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

