

L = 90° SYMBOL
 ● = PROPOSED WELLHEAD.
 ◆ = LANDING POINT.
 ○ = TARGET BOTTOM HOLE.
 ▲ = SECTION CORNERS
 LOCATED. (NAD 83)
 △ = SECTION CORNERS
 RE-ESTABLISHED.
 (Not Set on Ground.)
 (NAD 83)

The map displays a grid of land sections. Section 25 is at the top, followed by Section 36, and then Section 1 at the bottom. Key features include:

- Section 25:** Contains the "FOX CREEK 25 SE PAD - FOX CREEK 36-0560BE". A point is marked with an elevation of "Elev. Ungraded Ground = 5399.1'".
- Section 36:** Features a "Landing Point" marked with a diamond symbol.
- Section 1:** Includes a "Target Bottom Hole" marked with a circle symbol.
- Boundaries:** Each section is bounded by lines with bearings and distances. For example, the northern boundary of Section 25 is "S89°15'01\"W - 2643.85' (Meas.)".
- Monuments:** Several monuments are identified, including aluminum caps (#28285, #17492) and brass caps (1921). Their locations are given relative to road surfaces or ground elevations.
- Other Labels:** "R 63 W" and "R 62 W" are labeled near the top right corner. "T12N T11N" is labeled near the bottom right corner.

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S18°37'36"W	1143.46'



NAD 83 (SURFACE LOCATION)	NAD 83 (LANDING POINT)	NAD 83 (TARGET BOTTOM HOLE)
LATITUDE = 40°58'33.40" (40.975029°)	LATITUDE = 40°58'22.67" (40.972963°)	LATITUDE = 40°56'39.96" (40.944344°)
LONGITUDE = 104°22'39.10" (104.377528°)	LONGITUDE = 104°22'43.96" (104.378879°)	LONGITUDE = 104°22'43.88" (104.378856°)
NAD 27 (SURFACE LOCATION)	NAD 27 (LANDING POINT)	NAD 27 (TARGET BOTTOM HOLE)
LATITUDE = 40°58'33.40" (40.975046°)	LATITUDE = 40°58'22.73" (40.972980°)	LATITUDE = 40°56'40.02" (40.944451°)
LONGITUDE = 104°22'37.26" (104.377017°)	LONGITUDE = 104°22'42.12" (104.378367°)	LONGITUDE = 104°22'42.04" (104.378345°)
STATE PLANE NAD 83 (CO. NORTH)	STATE PLANE NAD 83 (CO. NORTH)	STATE PLANE NAD 83 (CO. NORTH)
N: 1600348.00° E: 3309955.65°	N: 599262.68° E: 3309596.51°	N: 158869.01° E: 3309734.21°
STATE PLANE NAD 27 (CO. NORTH)	STATE PLANE NAD 27 (CO. NORTH)	STATE PLANE NAD 27 (CO. NORTH)
N: 600345.56° E: 2311015.12°	N: 599260.26° E: 2309745.97°	N: 588866.78° E: 2309883.61°

BASIS OF BEARINGS
TRANSVERSE MERCATOR PROJECTION WITH
A CENTRAL MERIDIAN OF W105°00'00".

BASIS OF ELEVATION
OPUS SOLUTION GENERATED NAVD 88



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



HIGHPOINT OPERATING CORPORATION


FOX CREEK 25 SE PAD
FOX CREEK 36-0506BE
SW 1/4 SE 1/4, SECTION 25, T12N, R63W, 6th P.M.
WELD COUNTY, COLORADO

SURVEYED BY	GREG WEIMER, D.E.	08-20-18	SCALE
DRAWN BY	J.U.	08-31-18	1" = 1000'

WELL LOCATION PLAT

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE MONIES PREPARED FOR FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



REGISTERED LAND SURVEYOR
REGISTRATION NO. 28285
STATE OF COLORADO
09-20-18