

FORM  
2

Rev  
06/19

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401675297

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

07/05/2018

Well Name: LO\_SCHNEIDER

Well Number: 1414\_05H

Name of Operator: VERDAD RESOURCES LLC

COGCC Operator Number: 10651

Address: 5950 CEDAR SPRINGS ROAD

City: DALLAS State: TX Zip: 75235

Contact Name: Sydney Smith

Phone: (303)910-4511

Fax: ( )

Email: Regulatory@VerdadOil.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20170009

#### WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 14 Twp: 8N Rng: 60W Meridian: 6

Latitude: 40.669100

Longitude: -104.062516

Footage at Surface: 241 Feet FNL/FSL FNL 1343 Feet FWL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 4942

County: WELD

GPS Data:

Date of Measurement: 05/24/2018 PDOP Reading: 1.5 Instrument Operator's Name: Brent Garcia

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL  
300 FNL 2421 FWL 300 FSL 2424 FWL  
Sec: 14 Twp: 8N Rng: 60W Sec: 14 Twp: 8N Rng: 60W

#### LOCAL GOVERNMENT INFORMATION

County: WELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this COGCC application? If the local government has waived its right to precede the COGCC in siting determination, indicate by selecting "NO" here and selecting "Waived" below.

☐ Yes ☒ No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☐

The local government siting permit type is: \_\_\_\_\_

The local government siting permit was filed on: \_\_\_\_\_

The disposition of the application filed with the local government is: Waived

Additional explanation of local process:

WOGLA Submitted 05-13-2019

## LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

W2 Section 14 08N-60W 6th PM – 320 ACRES

Total Acres in Described Lease: 320 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 300 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 1343 Feet

Above Ground Utility: 1375 Feet

Railroad: 5280 Feet

Property Line: 241 Feet

School Facility: 5280 Feet

School Property Line: 5280 Feet

Child Care Center: 5280 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 362 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 300 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

WAITING ON SPACING ORDER DOCKET NUMBER TBD FOR FUTURE HEARING.  
SPACING UNIT CONFIGURATION:  
T8N-R60W-SEC.14: All  
ACRES: 640

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1097	640	ALL; Sec 14

## DRILLING PROGRAM

Proposed Total Measured Depth: 11263 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 840 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

PLEASE SEE WASTE MANAGEMENT PLAN ATTACHED TO ASSOCIATED FORM 2A.

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	80	70	80	0
SURF	13+1/2	9+5/8	36	0	1700	462	1700	0
1ST	8+1/2	5+1/2	20	0	11263	1505	11263	0

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

### GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

### RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

### OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

### OPERATOR COMMENTS AND SUBMITTAL

Comments	<p>The distance to the nearest well completed or permitted in the same formation was measured to the Schneider 1414-04H for a distance of 362 ft.</p> <p>The nearest proposed well belonging to another operator is the Pintail Fed 2-11-4HN (API 05-123-46547) measured in 2D at 840'.</p> <p>The nearest non op well was measured from Verdad SHL to Mallard BHL. The COGCC GIS mapping is showing incorrectly based on our well plats.</p>
----------	---

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ No \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 432178

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Sydney Smith

Title: Regulatory Manager Date: 7/5/2018 Email: ssmith@VerdadOil.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_

Director of COGCC

Date: 7/3/2019

Expiration Date: 07/02/2021

**API NUMBER**

05 123 50271 00

**Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**COA Type**

**Description**

	<p>1) Submit Form 42 online to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad.</p> <p>2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.</p> <p>3) Oil-based drilling fluid is to be used only after setting surface casing.</p> <p>Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.:</p> <p>1) All: Within 60 days of rig release, prior to stimulation.</p> <p>2) Delayed completion: 6 months after rig release, prior to stimulation.</p> <p>3) All: Within 60 days after first sales, as reported on the Form 5A, Completed Interval Report.</p>
	<p>Operator acknowledges the proximity of the listed offset well(s). Operator agrees to comply with the DJ Basin Horizontal Offset Policy to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, submit Form 42(s) ("OFFSET MITIGATION COMPLETED") for the mitigated well(s), stating that appropriate mitigation was completed prior to the hydraulic stimulation of this well.</p> <p>Offset wells to mitigate: 05-123-14241, BENNER E</p>

## **Best Management Practices**

<b>No</b>	<b><u>BMP/COA Type</u></b>	<b><u>Description</u></b>
1	Drilling/Completion Operations	Operator will perform anti-collision evaluation of all active (producing, shut-in, of temporarily abandoned) offset wellbores that have the potential of being within 150' feet of the proposed well prior to drilling operations. Notice shall be given to all offset operators prior to drilling.
2	Drilling/Completion Operations	Rule 604.c.1: Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections shall be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results shall be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.
3	Drilling/Completion Operations	Operator will comply with COGCC policy on bradenhead monitoring during Hydraulic Fracturing Treatment in the Greater Wattenberg Area per policy dated May 29, 2012.
4	Drilling/Completion Operations	Multi Well Open-Hole Logging – Rule 317.p: Alternative Logging Program: One of the first wells drilled on the pad will be logged with open-hole resistivity log and gamma-ray log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall state “Alternative Logging Program -No open-hole logs were run” and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.

Total: 4 comment(s)

## **Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.  
[http://cogcc.state.co.us/documents/reg/Policies/Wildlife\\_Notice.pdf](http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf)

## **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
401675297	FORM 2 SUBMITTED
401693886	OffsetWellEvaluations Data
401693889	DIRECTIONAL DATA
401693891	WELL LOCATION PLAT
401693892	DEVIATED DRILLING PLAN
401694158	SURFACE AGRMT/SURETY
402095682	OFFSET WELL EVALUATION

Total Attach: 7 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
OGLA	The Objective Criteria Review Memo (Doc# 2479099) is attached to the Form 2A associated with this APD. Following additional analysis arising out of the Objective Criteria, the Director determined that this application meets the standard for the protection of public health, safety, welfare, the environment and wildlife resources set by SB 19-181.	07/01/2019
Permit	With operator concurrence, the Local Government disposition and additional cultural distances were updated.	06/04/2019
Permit	Permitting review complete, passed Final Review.	05/23/2019
Permit	Corrected Longitude to -104.062516 to reflect Well Location Plat. Added Spacing Order Number 535-1097. Added Location ID Number 432178.  With operator concurrence, the following was corrected: Distance to Nearest Well was corrected to 362 ft. Lease Description and Acreage was corrected to W2 Section 14 08N-60W 6th PM – 320 ACRES. Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease was corrected to 300 ft. Distance to Nearest Well belonging to another operator was corrected.	05/21/2019
Permit	Passed Completeness.	07/06/2018

Total: 5 comment(s)