

STATE OF COLORADO  
OIL AND GAS CONSERVATION COMMISSION  
DEPARTMENT OF NATURAL RESOURCES



SUBMIT ORIGINAL AND 1 COPY

FOR OFFICE USE ONLY			
ET	FE	UC	SE

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir Use "APPLICATION FOR PERMIT—" for such proposals.)

<input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> COALBED METHANE <input type="checkbox"/> INJECTION WELL <input checked="" type="checkbox"/> OTHER		5 FEDERAL, INDIAN OR STATE LEASE NO.
2 NAME OF OPERATOR <b>Sunset Producing Co. c/o Arlian, Inc.</b>		6 PERMIT NO. <b>80-1429</b>
3 ADDRESS OF OPERATOR <b>1801 Broadway, Suite 1650</b>		7 API NO. <b>05-123-10091</b>
CITY STATE ZIP CODE <b>Denver, Colorado 80202</b>		8 WELL NAME <b>Franks</b>
4 LOCATION OF WELL (Report location clearly and in accordance with any State requirements See also space 17 below.) At surface <b>SW/4SE/4      660 FS</b>		9 WELL NUMBER <b>2</b>
At proposed production <b>SW/4SE/4      1980 FE</b>		10 FIELD OR WILDCAT <b>Heart</b>
12 COUNTY <b>Weld</b>		11 QTR. QTR. SEC., T.R. AND MERIDIAN <b>33-T9N-R61W</b>

Check Appropriate Box To Indicate Nature of Notice, Report or Notification

13A. NOTICE OF INTENTION TO: <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/> COMMINGLE ZONES <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> REPAIR WELL <input type="checkbox"/> OTHER _____	13B. SUBSEQUENT REPORT OF: <input checked="" type="checkbox"/> FINAL PLUG AND ABANDONMENT (SUBMIT 3RD PARTY CEMENT VERIFICATION AND JOB LOG) <input type="checkbox"/> ABANDONED LOCATION (WELL NEVER DRILLED. SITE MUST BE RESTORED WITHIN 6 MONTHS) <input type="checkbox"/> REPAIRED WELL <input type="checkbox"/> OTHER _____ <small>*Use Form 5 - Well Completion or Recompletion Report and Log for subsequent report of Multiple/Commingled Completions and Recompletions</small>	13C. NOTIFICATION OF: <input type="checkbox"/> SHUT-IN, TEMPORARILY ABANDONED (DATE _____) (REQUIRED EVERY 6 MONTHS) <input type="checkbox"/> PRODUCTION RESUMED (DATE _____) <input type="checkbox"/> LOCATION CHANGE (SUBMIT NEW PLAT) <input type="checkbox"/> WELL NAME CHANGE <input type="checkbox"/> OTHER _____
--	--	--

14. DESCRIBE PROPOSED OR COMPLETED OPERATIONS ON THIS FORM (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent  
**starting Jul-20-92**

15. DATE OF WORK \_\_\_\_\_

EXHAUSTED OIL WELL  
RECEIVED  
OCT 28 1993  
COLO. OIL & GAS CONS. COMM.

Set bridge plug at 6,516'.  
Set 2 sacks of cement on top of bridge plug.  
Perforated and cut 4 1/2" production casing at 5,862'.  
Pulled and laid down 4 1/2" production casing.  
Pumped 40 sacks of cement at 300'.  
Pumped 40 sacks of cement half-in and half-out of surface pipe at 195'.  
Placed 10 sacks of cement at top of surface pipe.  
Cut off surface pipe off 4' below ground and welded on steel cap.  
Removed deadmen, backfilled pits, cleaned up location.

*FINISHED CLEAN-UP 10-25-93 [Signature]*

16. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TELEPHONE NO. **292-4051**

NAME (PRINT) **Alvin R. (Al) Arlian** TITLE **Agent** DATE **10-26-93**

(This space for Federal or State office use)

APPROVED [Signature] TITLE **Sr. Petroleum Engineer** DATE **DEC 23 1993**  
**O & G Conservation Commission**

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

# invoice

*ADD Wireline Services*  
 17509 ROAD 14  
 FORT MORGAN, COLORADO 80701

(303) 867-2730

INVOICE DATE	INVOICE NO.	PAGE
7-21-92	79245	1

SOLD TO C R Payne  
 c/o Sunset Producing  
 P. O. Box 66  
 Roggen, CO 80652

SHIP TO Franks #1  
 Wildcat Field  
 Weld County CO

ORDER NO.	ORDER DATE	CUSTOMER NO.	SALES PERSON	PURCHASE ORDER NO.	SHIP VIA	SHIP DATE	TERMS

QUANTITY ORDERED	UNIT	ITEM NO.	ITEM DESCRIPTION	PRICE UNIT	UNIT PRICE
QUANTITY SHIPPED		QUANTITY BACKORD.		PER DISCOUNT	EXTENDED PRICE

7-20-92

Service Charge

CIBP @6516

2 sx Cement on W/P @6516

Cement Top Log

Cut 4 1/2" Casing @5862

**BEST IMAGE  
 AVAILABLE**

Price Per Bid

\$1600.00

THANK YOU



SALES AMOUNT	
MISC. CHARGES	\$1600.00
FREIGHT	
SALES TAX	
TOTAL	
PAYMENT REC'D	
BALANCE DUE	\$1600.00