



COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)

Notice of intention to drill _____	Note:
Notice of intention to change plans _____	This notice amends and corrects
Notice of date for test of water shut-off _____	a notice dated April 26, 1952,
Report on result of test of water shut-off _____	in which the well location
Notice of intention to re-drill or repair well _____	measurements and certain other
Notice of intention to clean out well _____	minor matters were set forth
Statement of shooting _____	incorrectly.
Statement of perforating _____	
Notice to pull or otherwise alter casing _____	
Notice of intention to abandon well <u>xxxx</u>	
Report of work done on well since previous report _____	

Following is a (~~notice of intention to do work~~) May 7 19 52
(report of work done) (On land) ~~(patented)~~ described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Wildcat (East Padroni)</u>
State	County	Field
<u>1</u>	<u>Rose Glassburn</u>	<u>14 SW/4</u>
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)
		<u>10N</u>
		(Twp.)
		<u>52W</u>
		(Range)
		<u>6 P.M.</u>
		(Meridian)

The well is located 2310 ft. ~~(N)~~ (N) of S. line and 1650 ft. (E) of W.
Line

The elevation above sea level is 4066 ft. ground level and 4076 ft. K. B.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Surface casing (10-3/4 O.D.) was set at 174' and cemented w/175 sx. with cement circulated. A 9" hole was drilled to 4900' and a rat hole of 6-1/8" was drilled from 4900 to 4940'. T D was 4940. Expected producing sands were dry w/top of "D" or Muddy at 4748' and top of "J" or Dakota at 4860', all measurements from K. B. Schlumberger electric log was run to 4919'.

Hole was filled with mud from 224' to total depth and a cement plug set from 134 to 224'. The surface pipe was then bull plugged and marked. Work completed 4-26-52.

Approved: MAY 12 1952
[Signature]
Director

Company A. A. BUCHANAN
Address P. O. BOX 2641, SAN ANTONIO 6, TEXAS
By [Signature]
Title LAND MANAGER

cc: Colorado Bureau of Mines
Museum Bldg., Denver 2, Colorado

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.