


COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well XXXX _____
 Report of work done on well since previous report _____

Following is a (notice of intention to do work) April 26, 19 52
 (~~report of work done~~) (On land) (patented) described as follows:

Colorado Logan Wildcat
 State County Field

1 Rose Glassburn 14 SW/4 10 N 52 W 6 PM
 (Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 2310 ft. (N) of south line and 990 ft. (E) of east
line of section 14 (S) (W)

The elevation above sea level is 4066 ft. Ground; 4076 KB

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Surface casing of 10 3/4" OD was set at 184' and cemented w/175 sacks of common cement. Cement circulated. A 9" hole was drilled from surface to 4900'. Rat hole of 6 1/8" was left from 4900-4940. TD was 4940'. Expected producing sands were dry. Top of "D" or Muddy was 4747. Top of "J" or Dakota was 4860. All measurements from KB. A 50 sack cement plug was placed at the bottom of the surface pipe and the surface pipe bull plugged and marked.

Approved: APR 28 1952

J. J. Zorichak
 Director at.

Company A. A. Buchanan

Address P.O. Box 2641, San Antonio, Te.

By Harry A. Trueblood, Jr.

Title Agent - Consulting Petroleum
Engineer - Sterling, Colo.

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

T