

Colorado Interstate Gas

LEASE: Young #24
FIELD: Young
COUNTY: Morgan
STATE: Colorado
LOCATION: 11 4N 58W
API #: 05-087-08055-00
SPUD DATE: 11/14/94
Rev. Date 07/16/19 - APT

ELEVATION: GL: 4,479' KB: 0

TD: 6,015' GL PBD: 5,957' GL

Size	ID
9-5/8	8.921
5-1/2	4.95

Perfs: 5,782'–5,806' GL w/ 8 SPF

PBD @ 5,957' GL

TD 7-7/8" hole @ 6,015' GL



2 jts 5-1/2", 15.5#, K55, 8R, ST&C csg w/ seal assembly stabbed into receptacle @ 84' GL

2 jts, 9 5/8", 36#, K55, 8R ST&C casing 0' – 84' GL swaged to 5-1/2" csg

7 jts, 13-3/8", 54.5#, K55, 8R, ST&C csg set @ 284' GL

Cemented surface w/ 250 sx, Standard cmt. Cmt Circ. Did not have good cmt around surf csg. Spotted 2-1/2 yds cmt from top of surf csg.

TD 17-1/2" Hole @ 299' GL

Cemented w/ 850 sx HLC and 250 sx 50/50 pox. Cmt Circ.

137 jts, 5-1/2", 15.5#, K55, 8R, LT&C casing set @ 6,005' GL