



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

(Indicate nature of data by checking below)

226-7

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report..... X

Following is a ~~(notice of intention to do work)~~ ~~(patented)~~ ~~(report of work done)~~ ~~(patented)~~ described as follows:
March 17, 1952

Colorado Logan Mt. Hope
State County Field
10 C. F. Green "B" SW/4 Section 19 9N 53W
(Well No.) (Lease) (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)
The well is located 998 ft. ~~(N)~~ of N Line and 330 ft. ~~(E)~~ of E Line
(S) (W)

The elevation above sea level is 4194 DF ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 2-1-52 Spudded. Ran and cemented 189', 8 5/8" surface casing at 202' with 110 sacks.
2-11-52 Drilled to TD 5040'. Ran Schlumberger survey. Cemented 4 1/2" casing at 5020' with 100 sacks.
2-13-52 Perforated 4885-86 with 4, 10 gram jets. Tested for water. No water recovered.
2-14-52 Perforated 4870-85 with 60, 10 gram jets. Ran 2" tubing.
2-15-52 Swabbed 20 bbls. load oil, 92 bbls. new oil, no water, 19 hours. Waiting on rods.
3-17-52 Pumped 91 bbls. oil, no water, 24 hours. COMPLETE

Schlumberger Tops: Niobrara 4054
'Muddy' 4865
Dakota 4969

Approved: MAR 18 1952

State Oil Inspector
DIRECTOR
Colorado Oil and Gas Conservation Commission
1136 Speer Blvd.
Denver 4, Colorado

Company Shell Oil Company

Address Denham Bldg., Denver, Colo.

By W. H. Inabnet
FOR J. E. GRAY

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate.

T