



Onshore Completion Report

Well Name: BOULTER 11-02

Report # 7.0, Report Date: 3/22/2012

API 05-123-14073	Prospect WATTENBERG	Regulatory Field WATTENBERG	State/Province COLORADO	Country USA
Block SWSW	Quarter Quarter SWSW	Section/Abstract 11	Township/Survey 4N	Range 65W
Well Configuration Type VERTICAL	Original KB Elevation (ft) 4,687.00	KB - GL / MSL (ftKB) 10	KB-Casing Flange Distance (ft)	KB-Tubing Head Distance (ft)
Report Start Date 3/22/2012	Report End Date 3/22/2012	Operations Summary IWP-250/350 BLOW THE WELL DOWN. PUMP 20 BBLs DOWN THE TUBING FOR WELL CONTROL. RIH AND TAG. RU THE POWER SWIVEL. HAVE NPT DELIVER 110 BBLs OF 2% KCL WATER WITH BIO-CIDE. START TO CLEAN OUT THE SAND PLUG. CLEAN OUT WITH 232 JTS AT 7097' THAT LEAVES 58' OF RAT HOLE. ROLL THE HOLE CLEAN. RD THE SWIVEL AND WASHINGTON HEAD. LAY DOWN 3 JTS. ND THE BOP. LAND THE TUBING WITH A MANDREL STYLE HANGER. CHANGE OUT THE O-RINGS, CASING VALVES AND MASTER VALVE. LAND THE TUBING AS FOLLOWS 229 JTS OF 2 3/8" 4.7# J-55 (7002.08') + NSN (1.10') + KB (8') LANDED AT 7011.18' THIS IS 13' ABOVE THE CODELL. HAVE LEED BOTTOM OUT THE WORK TANK. RIG DOWN MOVE OFF. HAD THE CAT HELP GET OFF LOCATION.		

Operations Next Report Period

WELL READY FOR THE SWAB RIG

Surface Casing Pressure (psi) 0.0	Tubing Pressure (psi) 250.0	Casing Pressure (psi) 350.0	Rig Time (hrs) 8.00
--------------------------------------	--------------------------------	--------------------------------	------------------------

Time Log

Start Time	End Time	Dur (hrs)	Rpt Code	Comment

Man Hrs

Company	Type	Count	Reg (hrs)	OT Sum (hrs)

Daily Costs

Task	Line	Int/Tan	Cost Description	LOE Des	Cost	Vendor	Note
03.3	00...	Intangi...	Completion Unit				
03.3	00...	Intangi...	Trucking Eqmt/Material				
03.3	00...	Intangi...	Company Labor & Expense				
03.3	00...	Intangi...	Completion Fluids				
03.3	00...	Intangi...	Rental-Other Misc				

Field Cost Summary by Description

Cost Description
Christmas Tree
Company Labor & Expense
Completion Fluids
Completion Unit
Downhole Equipment
Flowback
Fluid Disposal
Location-Site Prep/Maint
Perforating
Rental-Other Misc
Rent-Frac&Flowback Tank
Stimulation Treatment
Trucking Eqmt/Material
Tubing
Tubular Services

Field LOE Cost Summary

LOE Des	Cost

Attachments

Date	Description