

Newpek LLC		
API# 05-123-42868 Document No. 401315489 Operator No. 10484	Well Name: Fauver 1-20 Field: Wildcat Weld County, CO	NW 1/4 SW 1/4 SEC 20-T9N-R56W 6th PM Lat: 40.735669 Long: -103.666781
Cement Details	Current Wellbore Information	Hole Size\Casing

TOC: 0'  
BOC: 40'  
Conductor Depth: 40'  
Cement sxs: 30

Conductor Casing:  
Hole Size: 20"  
Casing: 16"

TOC: 0'  
BOC: 1522'  
Lead: 109 bbls, 2.54 ft3/sk,  
12 ppg  
Tail: 54 bbls, 2.22 ft3/sk,  
12.5 ppg  
Surface Csg Depth: 1522'

Surface Casing:  
Hole Size: 13.5"  
Casing: 9.625" 36# J-55 STC  
Ran 38 joints of casing

	SS	TVD
"Pierre Sst Marker"	1,513'	3,020'
Sharon Springs	276'	4,257'
Niobrara A	-464'	4,997'
Niobrara B	-535'	5,068'
Niobrara B2	-579'	5,112'
Base/B2	-620'	5,153'
Niobrara C	-658'	5,191'
Ft Hayes	-754'	5,287'
Codell (structural reference)	-800'	5,333'
Greenhorn	-963'	5,496'
Base X-Bentonite	-1,167'	5,700'
Dakota D	-1,271'	5,804'
Dakota J1	-1,355'	5,888'
Dakota J2	-1,374'	5,907'
Skull Creek Shale	-1,517'	6,050'
TD/PTD	-1,617'	6,150'

Niobrara C-2	PERF	5211'-5213', 5220'-5230', 5236'-5238' 2spf, 22 gram charge
Niobrara C-2		CIBP Set @ 5202'
Niobrara C-1	PERF	5169'-5176', 4 spf, 22 gram charge
Niobrara C-1	PERF	5182'-5192', 4 spf, 22 gram charge
Niobrara C-1		CIBP Set @ 5150'
Niobrara B	PERF	5058-68', 5074-84, 5095-5104, 5110-19, 2 spf 22 gram charges

TOC: 800'  
BOC: 6139'  
Lead: 90 bbls, 1.98 ft3/sk,  
12.7 ppg  
Tail: 50 bbls, 1.55 ft3/sk,  
13.5 ppg  
Intermediate Csg Depth: 6139'

Intermediate Casing:  
Hole Size: 8.75"  
Casing: 7" 26# L-80 LTC  
Ran 157 joints of casing



Total Depth: 6,150' MD

Date: 7/14/19 HLB