



Partner Summary Report

Date: 3/12/2019

Report #: 2

Well Name: SCHMIER B32-32

DOL:

Spud Date: 3/22/2009

Well Header

Well Name SCHMIER B32-32	API 05-123-29039	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB) ORIGINAL HOLE - 7,191.2	Current PBTD (ftKB) ORIGINAL HOLE - 7,115.5		
Spud Date 3/22/2009	TD Date 3/24/2009	Rig Release Date 3/25/2009	First Gas Sales				
Actual Latitude (°) 40.35580642	Actual Longitude (°) -104.58248601	Quarter 3 SW	Quarter 4 NW	Section 32	Township 5	Township N/S Dir N	Range E/W Dir W

Job: ABANDON , Job Start Date: 3/11/2019 06:00

Objective	AFE Number				
Report Start Date 3/12/2019 06:00	Report End Date 3/12/2019 12:30	Operations Summary CREW TO LOCATION, HELD SAFETY MTG. IWP: CSG 0 PSI, SURF 0 PSI. TIH W/ NC/XN NIPPLE +182 JTS 2 3/8 EUE 8RD 4.7# J-55 PRODUCTION TBG. ROLL HOLE CLEAN. MU TBG HANGER LAND IN WH. EOT @ 5641.49' KB. RD FLOOR, TONGS & SLIPS. ND BOPE, NU TOP FLANGE W/ MASTER VALVE. TEST PLUG & WH TO 1000 PSI FOR 15 MIN, GOOD TEST. SI SECURE WELL, RDMOL. NOTE: INSTALLED 5000 PSI VALVES ON CSG.			