



Partner Summary Report

Date: 3/15/2019

Report #: 3

Well Name: GUTTERSEN STATE D28-28D

DOL:

Spud Date: 4/28/2012

Well Header

Well Name GUTTERSEN STATE D28-28D	API 05-123-35121	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB) ORIGINAL HOLE - 7,187.6	Current PBTD (ftKB) ORIGINAL HOLE - 7,197.4		
Spud Date 4/28/2012	TD Date 4/30/2012	Rig Release Date 5/1/2012			First Gas Sales 6/5/2012		
Actual Latitude (°) 40.20241542	Actual Longitude (°) -104.55826490	Quarter 3 NE	Quarter 4 NW	Section 28	Township 3	Township N/S Dir N	Range E/W Dir W

Job: ABANDON , Job Start Date: 3/13/2019 06:00

Objective P&A			AFE Number
Report Start Date 3/15/2019 06:00	Report End Date 3/15/2019 18:00	Operations Summary CREW TO LOCATION. CONDUCT SAFETY MEETING. IWP: TBG 0#, CSG 0#, S/CSG 0#. BLED WELL PRESSURE DOWN.ND BOP/ 5K SPOOL. ND 3K WELL HEAD. NU 5K WELL HEAD WITH 5K CSG VALVES. NU BOP/ 5K SPOOL TIH WITH 2-3/8" NC / 2-3/8" X/N PROFILE NIPPLE + 188 JT'S OF 2-3/8" 4.7# J-55 TBG + 2-3/8" TBG MANDREL. ND BOP/ 5K SPOOL. NU 5K WELL HEAD. CIRCULATE HOLE CLEAN. TEST CIBP & CSG TO 1000# FOR 15 MIN'S. RELEASE PRESSURE. SIWH. REMOVED LOCK OUT TAG OUT OFF FLOW LINE. RDMO LOCATION WITH WORK OVER RIG / TANK & PUMP. CALLED PRODUCTION FOREMAN TO LET THEM KNOW RIG IS DONE. RC 425824821. CODE 247036.	