

Colorado Interstate Gas

LEASE: Latigo #36
FIELD: Latigo
COUNTY: Arapahoe
STATE: Colorado
LOCATION: 24 5S 61W
API #: 05-005-06362-00
SPUD DATE: 02/21/79
Rev. Date 08/20/19 - APT

ELEVATION: GL: 5,436' KB: 0'

TD: 6,782' GL PBTD: 6,752' GL

Size	ID
9-5/8"	8.921
5-1/2	4.95

[J-3] Perf: 6,704'–6,712' GL w/ 2 SPF

PBTD @ 6,752' GL

TD 7-7/8" hole @ 6,782' GL



2 jts 5-1/2" , 15.5#, K55 w/ seal assembly stabbed into receptacle @ 73' GL

2 jts, 9 5/8", 36#, K55, 8R casing (0' – 72') GL swaged to 5-1/2" csg

4 jts, 126', 13-3/8", 54.5#, K55, 8R csg (0'–126') GL swaged to 8-5/8" csg

TD 17-1/2" Hole @ 165' GL

Cemented surface w/ 625 sx, Class II. Cmt Circ.

21 jts, 872', 8-5/8", 24#, K55 csg (126'–1,001') GL

TD 12-1/4" Hole @ 1,010' GL

Cemented w/1,114 sx HLC + 225 sx 50/50 poz. Cmt Circ.

160 jts, 5-1/2", 15.5#, K55, 8R, LT&C @ 6,770' GL