

## Colorado Interstate Gas

**LEASE:** Latigo #19  
**FIELD:** Latigo  
**COUNTY:** Arapahoe  
**STATE:** Colorado  
**LOCATION:** 13 5S 61W  
**API #:** 05-005-06715-00  
**SPUD DATE:** 03/11/76  
**Rev. Date** 09/04/19 - APT

ELEVATION: GL: 5,443' KB: 0'  
 TD: 6,865' GL PBTD: 6,839' GL

Size	ID
9-5/8 *	8.921
5-1/2	4.95
2-3/8	1.995
Seating Nipple	1.78

\* Surface csg thought to be 36#, K55  
 based on delivery tickets, completion  
 report and collapse rating

Perf: 6,726'–6,754' GL w/4 SPF (07/13/04)  
 Perf: 6,734'–6,754' GL w/2 SPF [Original]

PBTD @ 6,839' GL

TD 7-7/8" hole @ 6,865' GL

