

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOBEST IMAGE
AVAILABLE

PLUGGING RECORD



INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Amerada Petroleum Corporation Field Swink Area Wildcat X
Lease Name J.M. Dunn Tract 1 Well No. 1 County Otero
Location NE, NE, Section 11 Township 24S Range 56W Meridian 6th PM
(Quarter Quarter)
610 feet from N Section line and 660 feet from E Section Line
N or S E or W

TOTAL DEPTH 4133' DATE OF PLUGGING 10/23/57

DETAILS OF WORK

Spotted cement plugs by Halliburton as follows:

3256-3159' with 30 sacks cement

824-648' " 25 " " (8-5/8" surface casing set at 784')

Plugged top of 8-5/8" casing with 10 sacks cement and welded plate marker on top of casing below plow level. (Location is in cultivated field)

(Verbal permit by telephone 10/22/57)

AJJ	
DVR	
FJK	
WRS	
HHM	
ALI	
JJD	
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

OCT 25 1957

Date

Company Amerada Petroleum Corp. Date 10/24/57

Address Box 1250, Casper, Wyo. Phone No. 3-3741

By R. D. Davidson Title Asst. Dist. Supt.
(Signature)

Director