

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED
OCT 14 1957

BEST IMAGE
AVAILABLE

SUNDRY NOTICES AND REPORTS ON WELLS



INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input checked="" type="checkbox"/>

(Check appropriate space)

LEASE NAME J. M. Dunn Tract 1 WELL NO. 1

FIELD Swink Area WILDCAT COUNTY Otero

LOCATION NE/4, NE/4 Section 11 Township 24S Range 56W Meridian 6th PM
(Quarter Quarter)

610 feet from N Section Line and 660 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

10-5-57 - Spudded 12-1/4" hole at 9:45 PM

10-8-57 - Ran 23 jts. 8-5/8" 2 1/2#, 8-Rt, Smls. casing set at 784' w/ Howco Float Shoe on bottom & Cents. at 778 & 724'. Cmt. casing by Howco w/ 400 sx 15.5# Ideal Reg. Cmt. Plug down at 10 AM w/ 500# press. Cmt. circ.

10-9-57 - Tested casing w/ 700# for 1/2 hr. - Held ok

AJJ	
DVR	
FJK	
WRS	
HH	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT 14 1957

Date
Director A. J. Jensen

Company Amerada Petroleum Corp. Date October 10, 1957

Address Box 1250 - Casper, Wyoming Phone No. 3-3711

By A. D. Davick Title Asst. Dist. Supt.
(Signature)