

COLORADO GAS CONSERVATION COMMISSION

No.

Rio Blanco County
Rangely Field

Well Log Record

Casing Record

Size	Feet
13 3/8"	65.60'
9 5/8"	1207.87
7"	1614
7"	4009
2 1/2"	6245.78'
	(Ldd.@6218.16')

Remarks:

Company Stanolind Oil & Gas Co.,

Lease E. E. Rector Lease. Well No. 6.

Location NE 1/4 Sec. 3 Twp. 1N Rge 102W-6th

Commenced 11/17/46 Completed 2/3/47.

Elevation 5194 RDB Tools used C Rotary

Initial Prod. 2/5/47. Bbls Oil

Bbls Water Cu. Ft. Gas

Log Furnished By J. M. Roe,
Field Superintendent.

Bottom	Total Ft.	Formation	Bottom	Formation
0	88	Gravel, sand and shale.		
2932	2844	Shale		
3068	136	Sandy Shale		
3183	115	Sand		
3730	547	Sandy Shale		
3853	123	Sand		
4160	307	Sandy Shale		
4544	384	Sand		
4758	214	Sandy Shale		
5589	831	Red Beds		
5603	14	Cap Rock		
6233	630	Weber Sand		
6233' T. D.				

Special Surveys:

Schlumberger Log from 1245 to 5605'

Lane Wells Log from 0 to 6233'

Temperature Surveys

Cement top behind 9 5/8" is 1050'.

Cement top behind 7" is 2000'.

Well was diamond cored: 5614 to 5668
drilled: 5668 to 5677
Cored: 5677 to 6233 T. D.

Complete Core analysis by Core Lab. Inc.

Schlumberger Tops.

Dakota	-- 3164
Morrison	-- 3241
Curtis	-- 3885
Entrada	-- 3987
Carmel	-- 4126
Navajo	-- 4195
Chinle	-- 4749
Shinarump	-- 4878
Moenkops	-- 4960
Weber	-- 5586

Permanent Bench Mark: Distance from RDB to
7" Ldg. Fl. is 10.80'

Elev. 7" Ldg. Fl. is 5183.20'