



00053146

COLORADO GAS CONSERVATION COMMISSION

No.

Rio Blanco County
Rangely FieldWell Log Record

Casing Record

Company Stanolind Oil & Gas Co.

Size	Feet	Lease	Associated "B"	Well No. 2
13 3/8"	406	Location	Sec. 3	Twp. 1N Rge 102W
13 3/8"	86	Commenced	7/7/47	Completed 9/20/47
7"	2867.10	Elevation	5788.95	Tools used C Rotary
7"	3956.97	Initial Prod.	244	Bbls Oil 100%
		Bbls Water		Cu. Ft. Gas
Remarks:		Log Furnished By	Stanolind Oil & Gas Co.	

Bottom	Formation	Bottom	Formation
0-40	Sand & Gravel		
40-55	Gravel		
55-80	Sand and Gravel		
80-1150	Shale		
1150-1182	Shale & Sand		
1182-1185	Sand		
1185-3027	Shale		
3027-3066	Sand & Shale		
3066-3140	Shale		
3140-3159	Sand		
3159-3185	Sand & Shale		
3185-3273	Sand		
3273-3324	Sand and Shale		
3324-3354	Shale		
3354-3450	Sand & Shale		
3450-3535	Shale		
3535-3755	Sand & Shale		
3755-3760	Sand		
3760-4117	Shale and Sand		
4117-4205	Sand		
4205-4223	Shale		
4223-4391	Shale & Sand		
4391-4519	Sand		
4519-4804	Sand and Shale		
4804-4836	Shale		
4836-5686	Red Beds		
5686-6289	Weber Sand		

All formations are taken from drilling reports.
 The Weber Sand was cored from 5701 to 6289
 Complete core analysis handled by Core Laboratory Inc.

Special Surveys:

One run of Schlumberger electrical log from 502 to 5698.
 Temperature Survey to determine top of cement behind 7" casing. Top
 of cement behind casing 2000'