

FORM
2

Rev
08/19

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401788630

Date Received:

04/11/2019

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER: _____

Refilling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: NILES MILLER

Well Number: 20-5HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: ERIN HAMPE

Phone: (720)929-3242

Fax: ()

Email: ERIN.HAMPE@ANADARKO.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 20 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.203992

Longitude: -104.794571

Footage at Surface: 319 Feet FNL/FSL FSL 829 Feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4955

County: WELD

GPS Data:

Date of Measurement: 11/30/2018 PDOP Reading: 1.2 Instrument Operator's Name: TRAVIS HOLLAND

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FSL 1052 FEL 50 FNL 1054 FEL
Sec: 20 Twp: 3N Rng: 66W Sec: 20 Twp: 3N Rng: 66W

LOCAL GOVERNMENT INFORMATION

County: WELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this COGCC application? If the local government has waived its right to precede the COGCC in siting determination, indicate by selecting "NO" here and selecting "Waived" below.

☒ Yes ☐ No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☒

The local government siting permit type is: WOGLA

The local government siting permit was filed on: 04/04/2019

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

Pad is located in unincorporated Weld County. Nearest town (Platteville) is >1500' from this location.

Weld County has waived it's ability to have the local permit precede the COGCC permits. However a WOGLA was submitted to Weld County on 4/4/2019. The WOGLA was approved on 8/7/2019.

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 3 North, Range 66 West, 6th P.M.
Section 20: SE/4
Weld County, Colorado

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building:	<u>563</u> Feet
Building Unit:	<u>592</u> Feet
High Occupancy Building Unit:	<u>5280</u> Feet
Designated Outside Activity Area:	<u>5280</u> Feet
Public Road:	<u>307</u> Feet
Above Ground Utility:	<u>289</u> Feet
Railroad:	<u>5280</u> Feet
Property Line:	<u>319</u> Feet
School Facility:	<u>5280</u> Feet
School Property Line:	<u>5280</u> Feet
Child Care Center:	<u>5280</u> Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 01/24/2019

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 200 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 1052 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

PROPOSED SPACING UNIT
03N66W SEC 29: N2NE;
03N66W SEC 20: E2;
03N66W SEC 17: SWSE, SESE
WELD COUNTY, COLORADO

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number: _____

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 13019 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 370 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Please refer to 2A for Disposal description.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	36.94	0	80	64	80	0
SURF	13+1/2	9+5/8	36	0	1500	590	1500	0
1ST	7+7/8	5+1/2	17	0	13009	1525	13009	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

PLEASE ENSURE ALL CORRESPONDENCE ASSOCIATED WITH THIS PERMIT GOES TO ANALYST AND DJREGULATORY EMAIL ADDRESSES, AS LISTED ON THIS PERMIT.

Offset well buffer description for the subject well has been attached to this permit for review (GIS BUFFER REVIEW/ANALYSIS).

The Niles Miller permitted wells were acquired via trade with PDC. The original well permits expired in April 2018 and were subsequently abandoned. These wells are being refiled with updated drill plans, spacing units, offset well evaluations...etc per KMG standards. The pad has not yet been built.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: ERIN HAMPE

Title: REGULATORY ANALYST Date: 4/11/2019 Email: DJREGULATORY@ANADARK

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved:  Director of COGCC Date: 9/7/2019

Expiration Date: 09/06/2021

API NUMBER

05 123 43147 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
Drilling/Completion Operations	This Permit to Drill is approved subject to all the BMPs and COAs on the most recently approved Form 2A and any subsequently approved Form 4 for the Oil and Gas Location. The most recently approved Form 2A and any subsequent Form 4s containing applicable COAs for this location shall be posted onsite during construction, drilling, and completions operations.
Drilling/Completion Operations	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad.</p> <p>2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.</p> <p>3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.</p>
Drilling/Completion Operations	<p>Operator acknowledges the proximity of the listed wells: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>05-123-15617 HSR-Beall 16-17 05-123-15756 HSR-Fine 3-20A 05-123-15919 HSR-Arnold 3-29A</p>
Drilling/Completion Operations	<p>Operator acknowledges the proximity of the following non-operated listed well: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>05-123-14115 Miller 4-20J</p>
Drilling/Completion Operations	<p>Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test:</p> <p>1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation.</p> <p>2) If a delayed completion, 6 months after rig release and prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation.</p> <p>3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.</p>

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Kerr-McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012
2	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling
3	Drilling/Completion Operations	317.p Open Hole Logging Exception: One of the first wells drilled on the pad will be logged with cased-hole neutron log with gamma-ray log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall state "Open Hole Logging Exception -No open-hole logs were run" and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.
http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

Attachment Check List

Att Doc Num	Name
401788630	FORM 2 SUBMITTED
401944985	WELL LOCATION PLAT
401945010	DIRECTIONAL DATA
401964734	GIS BUFFER REVIEW/ANALYSIS
401964746	SURFACE AGRMT/SURETY
401977811	EXCEPTION LOC WAIVERS
402003270	PROPOSED SPACING UNIT
402003620	OffsetWellEvaluations Data
402005066	OPEN HOLE LOGGING EXCEPTION
402005067	EXCEPTION LOC REQUEST
402005084	DEVIATED DRILLING PLAN
402169127	OFFSET WELL EVALUATION

Total Attach: 12 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Corrected form to be a refilled APD, added existing API, and added operator refilling comment to the submit tab with operator concurrence. Permitting Review Complete.	08/30/2019
Permit	The Objective Criteria Review Memo (Doc# 2316567) is attached to the Form 2A associated with this APD. Following additional analysis arising out of the Objective Criteria, the Director determined that this application meets the standard for the protection of public health, safety, welfare, the environment and wildlife resources set by SB 19-181.	08/27/2019
Permit	Removed operator BMPs related to the surface location with operator concurrence.	08/26/2019
Permit	Updated the Local Government Information with Final Disposition provided by the operator.	08/16/2019
Permit	Passed completeness.	06/14/2019
Permit	Returned to draft: Operator to complete Local Government Information. This form has not been reviewed for completeness.	05/30/2019

Total: 6 comment(s)