

## Colorado Interstate Gas

**LEASE:** Latigo #08  
**FIELD:** Latigo  
**COUNTY:** Arapahoe  
**STATE:** Colorado  
**LOCATION:** 24 5S 61W  
**API #:** 05-005-06214-00  
**SPUD:** 03/13/71 [Original]  
**SPUD:** 08/11/80 [Re-Entry]  
**Rev. Date** 09/09/19 - APT

ELEVATION: GL: 5,450' KB = GL + 7'  
 TD: 6,834' GL PBTD: 6,793' GL

Size	ID
5-1/2 - 14#	5.012
5-1/2 - 15.5#	4.95
2-3/8	1.995
Seating Nipple	1.78

Cemented w/300 sx 50/50 Poz + 200 sx  
 Type G  
 (Cmt. Circ.)

32 jts, 8-5/8", 24#, K55, R2, ST&C  
 @ 994' GL

TD 12-1/4" hole @ 998' GL

14# csg from 0' – 4,890' GL  
 15.5# csg from 4,890' – 6,834' GL

TOC @ 5,600' (Calculated)

218 jts, & 1 ea. 4', 6' & 10' subs 2-3/8", 4.7#,  
 J55, 8R, EUE tbg. Subs below 1<sup>st</sup> jt.

Seating Nipple @ 6,708' GL

Baker Model A-3 LOK-SET packer @ 6,713' GL  
 w/ 12,000# compression w/ wireline entry guide  
 on btm.

Perf: 6,730'–6,736' GL w/ 2 SPF [08/19/80]

Perf: 6,743'–6,751' GL w/ 2 SPF [Original]

PBTD @ 6,793' GL

TD 7-7/8" hole @ 6,834' GL

Cemented w/ 175 sx 50/50 poz.

209 jts, 5-1/2", 14# & 15.5#, K55, R2 ST&C @  
 6,834' GL