



## Partner Summary Report

Date: 3/21/2019

Report #: 2

Well Name: DR JOE CC06-09

DOL:

Spud Date: 10/29/2005

### Well Header

Well Name DR JOE CC06-09	API 05-123-23268	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (ftKB) ORIGINAL HOLE - 6,964.0		
Spud Date 10/29/2005	TD Date 11/2/2005	Rig Release Date 11/3/2005	First Gas Sales				
Actual Latitude (°) 40.33896349	Actual Longitude (°) -104.47288124	Quarter 3 NE	Quarter 4 SE	Section 6	Township 4	Township N/S Dir N	Range E/W Dir W

Job: ABANDON , Job Start Date: 3/20/2019 08:00

Objective P&A	AFE Number
------------------	------------

Report Start Date 3/21/2019 06:00	Report End Date 3/21/2019 19:00	Operations Summary CREW TO LOC, SIP 500/500/0, HOLD JSA SAFETY MTG, BLEED DOWN WELL, CONTROL WELL W/ 130BBL FRESH+BIO H2O, ND WELL HEAD, NU BOP STACK, PSI TEST HI LO, RU TO PULL TBG, TOOHLDOG W/ 30 JTS 2 3/8 EUE 8RD TBG, TALLY OOH SB 170JTS 2 3/8 TBG, HOLD JSA SAFETY MTG W/ CHS, RUWL, TIH SET 4 1/2 CIBP @ 6296FT, TOOHL W/ SETTING TOOL, TIH SPOT 2 SXS CMT ON TOP CIBP @ 6296FT, TOOHL W/ BAILER, RDWL, ND BOP AND 4 1/2 X 3K WELL HEAD, NU 5K WELL HEAD W/ NEW 5K SIDE VALVES AND XX NIPPLES, NU BOP, TIH LAND TBG W/ MANDRILL/SN/NC @ 5555.06FTKB, NU NEW 5K MASTER VALVE, LOAD HOLE W/ 70BBL FRESH +BIO H2O, PSI TEST CSG/CIBP TO 500PSI HOLD F/ 15 MIN [HOLDING], RELEASE PSI , OPEN TBG AND CSG LET FLUID BALANCE TO LOWER FLUID LEVEL, SECURE WELL, DRAIN EQUIPMENT, SDFN
--------------------------------------	------------------------------------	--