



COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS

RECEIVED  
JUN 5 1952  
OIL & GAS  
CONSERVATION COMMISSION

226-16

(Indicate nature of data by checking below)

- Notice of intention to drill \_\_\_\_\_
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well \_\_\_\_\_
- Report of work done on well since previous report X \_\_\_\_\_

Following is a ~~(notice of intention to do work)~~ June 4 1952  
(report of work done) ~~(On land)~~ (patented) described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Mt. Hope</u>
State	County	Field
<u>16</u>	<u>C.F.Green "A"</u>	<u>NW/4 Section 30</u>
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)
		<u>9N</u>
		(Twp.)
		<u>53W</u>
		(Range)
		(Meridian)

The well is located 330 ft. (N) of N. Line and 990 ft. (E) of W. Line.  
(S) (W)

The elevation above sea level is 4193 D.F. ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

6-3-52 Loaded hole with 106 barrels of oil. Perforated 4909-4910 with 4 jets to test cement job. Bailed 2 barrels of water. Water exhausted. Cement job okay. Perforated 4965-80 with 60 jets. Ran tubing.

6-4-52 Swabbed and flowed 80 barrels of load oil. Then flowed 390 barrels of new oil and no water in 24 hours through 2" tubing. Complete.

Schlumberger Formation Tops: Muddy 4856 feet, Dakota 4962 feet, Lakota 5218 feet, Morrison 5362 feet, Permian 5684 feet, Big Blue 6256 feet, Pennsylvanian 6707 feet, Topeka 6745 feet, Deer Creek 6794 feet, Lansing-Kansas City 6842 feet, Marmaton 7071 feet, Pre-Cambrian 7726 feet.

Approved: JUN 5 1952  
[Signature]  
Director

Company Shell Oil Company  
Address 413 Denham Bldg. Denver, Colo.  
By [Signature]  
Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.